

US ROCKIES REGION

Anadarko Daily Summary Report

Well: HSR-FEDERAL 15-36

Project: COLORADO-WELD-NAD83-UTM13

Site: USA 15-36 PAD

Rig Name No: BAYOU 14/14

Event: CONST- CAP WELL WORK

Start Date: 8/4/2014

End Date: 8/6/2014

Spud Date: 3/21/1990

Active Datum: RKB @5,003.00usft (above Mean Sea Level)

UWI: SW/SE/0/3/N/66/W/36/0/0/6/PM/S/660.00/E/0/1,980.00/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	08/04/2014		MIRU BWS # 14, SIP 0 PSI 4.5" CSG, O SURF, ND WELLHEAD, NU BRAIDEN HEAD
2	08/05/2014		RIH W/ 1.66" TBG, CIRC DN TO 1557', RU SANJEL, PUMP 215 SX OF TYPE 3 CMT, PUH TO 500', REVERSE OUT, SD TBG, ND BOP, LAND CSG
3	08/06/2014		RUN CCL,CBL,VDL,GR, TOC @ 502', NU 5K WELLHEAD, INSTALL BOP