

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
400663769

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☐ MULTIPLE ZONES ☒ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

Well Name: Easy Come Well Number: # 1
Name of Operator: WIEPKING-FULLERTON ENERGY LLC COGCC Operator Number: 96340
Address: 4600 S DOWNING ST
City: ENGLEWOOD State: CO Zip: 80113
Contact Name: Tim Herian Phone: (316)655-9200 Fax: ()
Email: therian1@cox.net

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20090067

WELL LOCATION INFORMATION

QtrQtr: NENE Sec: 2 Twp: 6S Rng: 54W Meridian: 6
Latitude: 39.564410 Longitude: -103.399820

Footage at Surface: 620 feet FNL/FSL FNL 853 feet FEL/FWL FEL

Field Name: WILDCAT Field Number: 99999

Ground Elevation: 5176.72 County: LINCOLN

GPS Data:

Date of Measurement: 07/21/2014 PDOP Reading: 2.5 Instrument Operator's Name: Elijah Frane

If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Lots 1, 2, S/2NE, SENW, Section 02, T6S-R54W

Total Acres in Described Lease: 238 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 620 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 4525 Feet

Above Ground Utility: 5095 Feet

Railroad: 5280 Feet

Property Line: 620 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 1477 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 5280 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CRETACEOUS	CRTC			
MISSISSIPPIAN	MSSP			
PENNSYLVANIAN	PENN			

DRILLING PROGRAM

Proposed Total Measured Depth: 8400 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 1477 Feet (Including plugged wells)

Will a closed-loop drilling system be used? No

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☐ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Drilling pit

Other Disposal Description:

Water based bentonitic drilling fluids, except deminimus amounts, will be removed from the drilling pit and disposed in accordance with the 900 series rules.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	300	200	300	0
1ST	7+7/8	5+1/2	17	0	8400	300	8400	5500

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

No Conductor Casing will be used.
There is an indicated surface water area approximately 585' northeast of the proposed well stake and in the wheat stubbel.
A barbed wire fence located 620' north and 853' east of well pad. The nearest water well is shown to be 1973' south of this location and according to the surface owner has never be used. The condition of the well prevents any sampling.
A non-occupied structure, grain bins lies 5414' to the southwest of this location.
County roads with overhead power lines lie south and west of this location.
None of the above will be disturbed by drilling operations.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Tim Herian _____

Title: agent _____ Date: _____ Email: therian1@cox.net _____

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC _____ Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Storm Water/Erosion Control	<p>BMP Plan</p> <p>Wiepking-Fullerton Energy, L.L.C. 4600 S. Downing St., Englewood, CO 80113 303-789-1798 (phone), 303-761-9067 (fax)</p> <p>Certification to Discharge Under CDPS General Permit COR-03000 Stormwater Discharges Associated with Construction</p> <p>Certification Number COR 39788</p> <p>Easy Come # 1 well T6S, R54W Sec. 02: NE1/4NE1/4 Lincoln County, Colorado</p> <p>Description of the Well Site and Construction Area. A 1-3 acre site with access road for the drilling of an oil and gas well. The well site is on farm ground with wheat stubble. There is an indicated surface water area 402' northwest of the proposed well pad. A dirt brim will be installed on the south and west sides of the well pad to protect this area. Surface Roughening will also be used on any low side of drill site to reduce the speed of runoff, increase infiltration, reduce erosion, trap sediment and prepare soil for reseeding. Drilling pits closed and reclaimed within 3 months weather permitting. Topsoil will be separated and spread on drill site as final operation before reseeding operations which will be completed within 6 months weather permitting. To prevent soil erosion site will be disked and straw crimped in or manure spread.</p> <p>Stormwater Management Plan (SWMP) is on file in Wiepking-Fullerton Energy, L.L.C. office.</p> <p>Spill Prevention, Control and Countermeasure Plan are on file in Wiepking-Fullerton Energy, L.L.C. office.</p>

Total: 1 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400663937	OTHER
400663945	30 DAY NOTICE LETTER
400663954	PROPOSED BMPS
400663958	TOPO MAP
400663961	WELL LOCATION PLAT

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)