

Current Wellbore Diagram

Best Information as of 8/1/14

Elev. GL: 4634'
KB: 4642'

Spud: 7/13/1982
Comp: 8/22/1982

8-5/8", 24#
Set @ 118'

Top of Cement @ \pm 3000'

Production Casing
5-1/2" 14# J-55
set @ 5018' w/300 sx

Hole size 7-7/8" to TD

4928' perforated w/2 SPF

4932'

PBTD @ 4945'

TD: 5021'

Markus Production, Inc.

Jolly 41X-6

NE/NE Section 6-T3S-R55W
Washington County, Colorado
API# 05-121-09826

PxA Intent Wellbore Diagram

Best Information as of 8/15/14

Elev. GL: 4634'
KB: 4642'

Spud: 7/13/1982
Comp: 8/22/1982

8-5/8", 24#
Set @ 118'

15 sx Surface Plug

50 sx Sf Csg Plug 70'-170'

40 sx Stub Plug 2450'-2550'

Cut casing @ ~ 2500'

Hole size 7-7/8" to TD

Top of Cement @ \pm 3000'

Production Casing
5-1/2" 14# J-55
set @ 5018' w/300 sx

CIBP set @ 4875' w/2 sx cmt on tc

4928' perforated w/2 SPF

4932'

PBTD @ 4945'

TD: 5021'

Markus Production, Inc.
Jolly 41X-6

NE/NE Section 6-T3S-R55W
Washington County, Colorado
API# 05-121-09826