

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400630652

Date Received:

07/15/2014

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refiling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: SRC Wiedeman

Well Number: 21-5-3CHZ

Name of Operator: SYNERGY RESOURCES CORPORATION

COGCC Operator Number: 10311

Address: 20203 HIGHWAY 60

City: PLATTEVILLE State: CO Zip: 80651

Contact Name: Sonia Spencer

Phone: (720)420-5749

Fax: (720)420-5800

Email: sonia.spencer@iptenergyservices.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20090043

WELL LOCATION INFORMATION

QtrQtr: NWNE Sec: 5 Twp: 5N Rng: 66W Meridian: 6

Latitude: 40.433356

Longitude: -104.801710

Footage at Surface: 1393 feet FNL/FSL FNL 2438 feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4783

County: WELD

GPS Data:

Date of Measurement: 03/26/2014 PDOP Reading: 1.6 Instrument Operator's Name: Brett Birch

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL

871 FNL 2178 FEL 871 FNL 2155 FWL
Sec: 5 Twp: 5N Rng: 66W Sec: 3 Twp: 5N Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.
(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

See lease map.

Total Acres in Described Lease: 11 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 665 Feet
Building Unit: 923 Feet
High Occupancy Building Unit: 1435 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 995 Feet
Above Ground Utility: 229 Feet
Railroad: 5280 Feet
Property Line: 200 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 05/16/2014

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 170 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Codell
NE/4 Section 5, T5N-R66W, N/2 Section 4, T5N-R66W, NW/4, Section 3, T5N-66W.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		640	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 17035 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 80 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: ONSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	1200	994	1200	0
1ST	8+3/4	7	26	0	7600	712	7660	3000
1ST LINER	6+1/8	4+1/2	13.5	7460	17035			

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This is one Form 2 out of 8 submitted for new Horizontal Wells.
Attach is the Letter to the Director for Surface Owner Exception Location.
The Anti-Collision Waiver-Rule 318.A.m- Attached as " other"

Distance to nearest permitted or existing wellbore penetrating objective formation is the Kelly Farms 21-4-3NHZ API 05-123-38139

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Sonia Spencer

Title: Project Mgmt Permitting Date: 7/15/2014 Email: sonia.spencer@iptenergyservic

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 8/19/2014

Expiration Date: 08/18/2016

API NUMBER

05 123 40069 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	<p>Operator acknowledges the proximity of the listed wells: Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>SRC 31-5D (API NO 123-30075)SRC NORTHRIDGE 11-4D (API NO 123-29617) SRC NORTHRIDGE 12-4D (API NO 123-29618)SRC NORTHRIDGE 21-4D (API NO 123-29619) SRC NORTHRIDGE 22-4D (API NO 123-29620)SRC NORTHRIDGE 4KD (API NO 123-29657)</p>
	<p>Operator acknowledges the proximity of the listed well: Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>GREELEY TECH CENTER 41-5 (API NO 123-11455)</p>
	<p>Operator shall comply with Buffer Zone Move-In, Rig-Up Notice Policy dated 12-16-2013.</p>
	<p>1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Run and submit Directional Survey from TD to base of surface casing. The operator shall comply with Rule 321, and it shall be the operator's responsibility to ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.</p>

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	Anti-Collision Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed wells. The anti-collision scan may include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed well-path with its respective error of uncertainty. If current surveys do not exist for the offset wells, operators may have gyro surveys conducted to verify bottom-hole location. The proposed well may only be drilled if the anti-collision review results indicate that the risk of collision is sufficiently low as defined by the anti-collision plan, with separation factors greater than 1.5, or if the risk of collision has been mitigated through other means including shutting in wells, plugging wells, increased drilling fluid in the event of lost returns or as is appropriate for the specific situation. In the event of an increased risk of collision, that risk will be mitigated to prevent harm to people, the environment or property. For the proposed well, upon conclusion of drilling operations, an as-constructed directional survey will be submitted to the COGCC with the Form
2	Drilling/Completion Operations	Operator acknowledges and will comply with COGCC Policy for Braden-head Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
3	Drilling/Completion Operations	Open hole resistivity log with gamma ray will be run on one of the first wells drilled on this pad to describe the stratigraphy of the vertical section of the wellbore and to adequately verify the setting depth of the surface casing and aquifer coverage. The Drilling Completion Report-Form 5 for every well on the pad shall identify which well was logged.

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

Att Doc Num	Name
2157778	SURFACE AGRMT/SURETY
2157779	LEASE MAP
2157780	SURFACE OWNER LIST/MAP
400630652	FORM 2 SUBMITTED
400634646	DIRECTIONAL DATA
400634659	DEVIATED DRILLING PLAN
400634665	WELL LOCATION PLAT
400634671	EXCEPTION LOC REQUEST
400637007	OffsetWellEvaluations Data
400642863	PROPOSED SPACING UNIT
400645210	ANTI-COLLISION WAIVER

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comments. Final Review-passed.	8/18/2014 4:29:28 PM
Permit	Oper. corrected lease acres and submitted lease map. Oper. submitted redacted SUA and map of lands covered by SUA.	8/12/2014 2:57:02 PM
Permit	Oper. submitted corrected dist. to nearest well permitted & penetrated.	8/11/2014 9:43:14 AM
Engineer	Offset Wells Evaluated.	7/29/2014 1:39:34 PM
Permit	Passed completeness.	7/16/2014 11:21:25 AM

Total: 5 comment(s)