

Tyson S Foutz

From: Williamson, Craig <cwilliamson@blm.gov>
Sent: Wednesday, July 9, 2014 9:28
To: tyson@foutzconsulting.com
Cc: Craig Burger - DNR
Subject: Re: SWEVCO Federal O-22 verbal needed for abandonment

Tyson,

I agree with Craig B entirely. In addition, we require a 120' plug across the top of the tubing fish. WOC and tag. Then plug from 680' to surface.

Please follow up with a Sundry including the new procedure attached.

Craig

On Tue, Jul 8, 2014 at 7:08 PM, Tyson S Foutz <tyson@foutzconsulting.com> wrote:

Craigs,

We have pumped 5 squeeze jobs and been fishing for three days. Our last run removed all of the cut-rite from our turnover shoe, so now we have what we suspect is a split collar spinning around on our cement with the added fun of cut-rite to mill through. Given the low likelihood that this fish can be recovered quickly or without causing casing damage, SWEVCO requests permission to abandon. Since there is already so much cement in the well, the procedure only calls for a surface plug. Let me know if more will be required.

Feel free to call with any questions or comments. We would like to begin operations tomorrow morning, Wednesday July 9th, 2014 if possible.

Regards,

Tyson Foutz, P.E.

tyson@foutzconsulting.com

+1.505.320.6275

--

Craig Williamson
Petroleum Engineer
Bureau of Land Management
White River Field Office
Office: (970) 878-3814
Cell: (720) 273-3465