

Williams Et Al 24-1

1980 FSL720 FWL NWSW 24 5N 61W 6th PM
Lat 40.38493 Long -104.16353 (from footages)
Weld County, Colorado
API #05-123-09642

Spud date 12/23/1978

4588 KB
4576 GL

0'

Surface plug as needed

Water 1430'
(Within 1 mile radius)

8.625", 24#/ft Wt, Grade, 176', 10.75" hole
Cemented to surface w/ 175 sx.

400 sx shoe plug to surface
700 '

As found in well:
Williams Et Al 24-1,

2890 '

300sx OH Plug

3400 '

TOC N/A

Niobrara 5912 '

Carlile 6135 '

Greenhorn 6178 '

D Sand 6505 '

J Sand 6567 '

7 7/8" hole
No Prod Casing

PBTD -- ft
TD 6597 ft 1/1/1979

Updated 7/29/2014 jad