

<b>FORM 5A</b> Rev 06/12	<b>State of Colorado</b> <b>Oil and Gas Conservation Commission</b> 1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:25%;">DE</td> <td style="width:25%;">ET</td> <td style="width:25%;">OE</td> <td style="width:25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
<b>COMPLETED INTERVAL REPORT</b>			Document Number: 400662598  Date Received:				
The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.							

1. OGCC Operator Number: <u>8960</u> 2. Name of Operator: <u>BONANZA CREEK ENERGY OPERATING COMPANY</u> 3. Address: <u>410 17TH STREET SUITE #1400</u> City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>	4. Contact Name: <u>Olga Chikaloff</u> Phone: <u>(720) 440-1600</u> Fax: <u>(720) 279-2331</u> Email: <u>ochikaloff@bonanzacrck.com</u>
--	--

5. API Number <u>05-123-38910-00</u> 7. Well Name: <u>Antelope</u> 8. Location: QtrQtr: <u>SESW</u> Section: <u>20</u> Township: <u>5N</u> Range: <u>62W</u> Meridian: <u>6</u> 9. Field Name: <u>WATTENBERG</u> Field Code: <u>90750</u>	6. County: <u>WELD</u> Well Number: <u>24-21-20HC</u>
--	--

**Completed Interval**

FORMATION: <u>CODELL</u>	Status: <u>PRODUCING</u>	Treatment Type: <u>FRACTURE STIMULATION</u>
Treatment Date: <u>05/14/2014</u>	End Date: <u>05/15/2014</u>	Date of First Production this formation: <u>05/26/2014</u>
Perforations Top: <u>7045</u>	Bottom: <u>11089</u>	No. Holes: _____ Hole size: _____
Provide a brief summary of the formation treatment:		Open Hole: <input checked="" type="checkbox"/>
18 Stage Codell pumped a total of 57,207 bbls of fluid (Phaser) and 4,275,060 # of sand (40/70 Ottawa, 30/50 Ottawa, 20/40 PropStar); ATP 3,968 psi, ATR 50.00 bpm, Final ISDP 3,375 psi; completed with sliding sleeves and casing packers.		
This formation is commingled with another formation: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Total fluid used in treatment (bbl): <u>57207</u>	Max pressure during treatment (psi): <u>4888</u>	
Total gas used in treatment (mcf): _____	Fluid density at initial fracture (lbs/gal): <u>8.33</u>	
Type of gas used in treatment: _____	Min frac gradient (psi/ft): <u>0.95</u>	
Total acid used in treatment (bbl): _____	Number of staged intervals: <u>18</u>	
Recycled water used in treatment (bbl): _____	Flowback volume recovered (bbl): <u>26258</u>	
Fresh water used in treatment (bbl): <u>57207</u>	Disposition method for flowback: <u>DISPOSAL</u>	
Total proppant used (lbs): <u>4275060</u>	Rule 805 green completion techniques were utilized: <input checked="" type="checkbox"/>	
Reason why green completion not utilized: _____		

**Fracture stimulations must be reported on FracFocus.org**

**Test Information:**

Date: <u>05/30/2014</u>	Hours: <u>72</u>	Bbl oil: <u>1017</u>	Mcf Gas: <u>783</u>	Bbl H2O: <u>1119</u>
Calculated 24 hour rate:	Bbl oil: <u>339</u>	Mcf Gas: <u>261</u>	Bbl H2O: <u>373</u>	GOR: _____
Test Method: <u>Flowing</u>	Casing PSI: <u>975</u>	Tubing PSI: <u>330</u>	Choke Size: <u>20/64</u>	
Gas Disposition: <u>SOLD</u>	Gas Type: <u>WET</u>	Btu Gas: <u>1311</u>	API Gravity Oil: <u>43</u>	
Tubing Size: <u>2 + 3/8</u>	Tubing Setting Depth: <u>6910</u>	Tbg setting date: <u>05/20/2014</u>	Packer Depth: _____	
Reason for Non-Production: <span style="border: 1px solid black; display: inline-block; width: 600px; height: 20px;"></span>				
Date formation Abandoned: _____	Squeeze: <input type="checkbox"/> Yes <input type="checkbox"/> No	If yes, number of sacks cmt _____		

\*\* Bridge Plug Depth: \_\_\_\_\_      \*\* Sacks cement on top: \_\_\_\_\_      \*\* Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Olga Chikaloff  
Title: Engineering Technician Date: \_\_\_\_\_ Email: ochikaloff@bonanzacrk.com  
:

### **Attachment Check List**

**Att Doc Num**      **Name**

--	--

Total Attach: 0 Files

### **General Comments**

**User Group**      **Comment**      **Comment Date**

--	--	--

Total: 0 comment(s)