

This well is P & A: May 30, 2014



GUNNISON ENERGY CORPORATION
AN OXBOW COMPANY

SPAULDING PEAK 1294-23-41
1204' FNL, 1307' FEL, Sec. 23, T12S, R94W
Delta County, Colorado
API# 05-029-06084

proposed plugs

note 4 1/2 CBL top unknown because casing was not full.
Cement seen to surface but fell back

16" @ 68'
Plug 4 required 31 sxs,cmt to surf on all annuli
Plug 3 tagged at 256 ft
9-5/8", 26 lb/ft, H-40 @ 465'

Plug 4 surface plug 200 ft
cement plug on surface 200 ft
fill annulus void, 16 sx w top up.

Plug 3 600-200 ft
cement plug tagged 400 ft. tall
31 sacks 15.8 ppg cement

7" DV @ 614'

7", 17.0 lb/ft, H-40 @ 1487'
Plug 2 tagged at 1360 ft

PLUG 2 1700 to 1300 ft
cement plug tagged 400 ft. tall
31 sacks 15.8 ppg cement

Marker Joint 1977'-1997'
Plug 1 tagged at 1802 ft

PLUG 1 2206 to 1800 ft
cement plug tagged 400 ft. tall

FISH 2206 ft Unknown fish Unable to recover. !

tagged

Perforations: 2362'-2372'
2380'-2406'

tagged

Perforations: 2530'-2548'
2560'-2580'

tagged

4-1/2" DV @ 2672'

PBTD 3094'
4-1/2", 11.6 lb/ft, J-55 @ 3098'
Weatherford OH Packer; Top of Pkr @ 3102'
Top of Rubber @ 3110'; Bottom @ 3115'

OH to 3685'

Cement Circulated to surface on
all strings of casing and conductor

