

Berry Petroleum Company
Latham 32-30D
05-045-13689-0000
NWNW Sec 32 Twn 5S Rng 96W
Garfield County, Colorado

Prepared Heidi Bang
Updated 8/12/2014

Rig Frontier 10

8275 KB
8253 GL
22 KB-GL

261 BHT

20" Conductor @ 120'

16" hole @ 2368'

54 jts 9-5/8" 36# J-55 @ 2311' w/ 1.9" PS, inj port 2092'

cmtd 1204 sx lead @ 11.0 ppg, 2.67 yield & 107 sx tail @ 12.5 ppg, 1.67 yield

TOC @ 4260'

Equipment in Hole	Qty	Length	Depth
KB		28.00	28.00
Tbg Hanger		0.80	28.80
2-3/8" 4.7# N-80 Tbg	65	2108.75	2137.55
Yellow	200	6968.72	9106.27
SN 1.78		1.10	9107.37
Yellow	1	32.50	9139.87
Pump Off Bit Sub		0.65	9140.52
EOT			9140.52

TOCC @ 7316'

9/8/2008 Spud
9/11/2008 Set Surf
9/17/2008 Set Prod
9/15/2009 PTST 6200# @ PBTD
9/23/2009 Frac Stg 1-7
9/27/2009 CT D/O CFP
10/7/2009 Land Tbg
8/5/2014 Cleaned out to 9675'

Stage 8

7722 - 7825', total 30 shots @ 2 spf
Frac'd w/ 99859 lb 30/50 white, 5528 bbl & 500 g 7.5% acid

Stage 7

7858 - 8066', total 30 shots @ 2 spf
Frac'd w/ 130970 lb 30/50 white, 6967 bbl & 500 g 7.5% acid

Stage 6

8110 - 8310', total 30 shots @ 2 spf
Frac'd w/ 106700 lb 30/50 white, 5817 bbl & 500 g 7.5% acid

Stage 5

8365 - 8561', total 30 shots @ 2 spf
Frac'd w/ 82493 lb 30/50 white, 4671 bbl & 500 g 7.5% acid

Stage 4

8606 - 8774', total 30 shots @ 2 spf
Frac'd w/ 81363 lb 30/50 white, 3990 bbl & 500 g 7.5% acid

Stage 3

8826 - 9081', total 24 shots @ 2 spf
Frac'd w/ 106744 lb 30/50 white, 3050 bbl & 500 g 7.5% acid

Stage 2

9151 - 9321', total 24 shots @ 2 spf
Frac'd w/ 122269 lb 30/50 white, 3613 bbl & 500 g 7.5% acid

Stage 1

9399 - 9536', total 24 shots @ 2 spf
Frac'd w/ 77323 lb 30/50 white, 2382 bbl & 500 g 7.5% acid

Marker Jts @
4914-34' & 7287-7315'

8-3/4" hole @ 7468' & 7-7/8" hole @ 9832'

230 jts 4-1/2" 11.6# I-80, P-110 & NS-110 prod csg @ 9776', FC @ 9730'
cmtd 678 sx TXI @ 12.0 ppg, 2.14 yield

PBTD @ 9702' WL Tag 12/17/08
CT C/O @ 9702' on 9/27/09