

## US ROCKIES REGION

**Anadarko Daily Summary Report**

Well: VON FELDT 14-12

Project: COLORADO-WELD-NAD83-UTM13

Site: VON FELDT 14-12

Rig Name No: BAYOU 14/14

Event: CONST- CAP WELL WORK

Start Date: 8/13/2014

End Date: 8/20/2014

Spud Date: 3/18/2005

Active Datum: RKB @4,855.99usft (above Mean Sea Level)

UWI: 0/2/N/67/W/12/0/SWSE/6/0/S/-600/W/0/-2100/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	10/01/2013		RU CANARY WIRELINE SLVT - RIH VAUGHN ENERGY SERVICES GYRO TOOL TO 7700' MAKING STOPS EVERY 100' RDMO
2	08/13/2014		MIRUSU, BWS #14, WAIT ON VAC TRUCKS, MECH TROUBLE W/ SUPER VAC, SIWFN
3	08/14/2014		KILL WELL, SIP 650 TBG 650 ANN 0 SURF, NU BOPS, EMI TBG, 254 JTS GOOD, 1 BAD, TIH W/ MST AND RBP SET @ 4120', ROLL GAS OUT, TEST CSG TO 2000 PSI, GOOD TEST 15 MIN, POOH W/ 62 STDS AND MST, SD DUE TO WEATHER
4	08/15/2014		FINISH STDING BK TBG, NU DUAL ENTRY FLANGE, TIH W/ 1.66, CONDITION HOLE FOF CMT, PUMP 775 SXS OF 15.8# CLASS G CMT FROM 4000'-550', POOH TO 550', REVERSE OUT, POOH W/ REMAINING 1.66" TBG, DN DUAL ENTRY FLANGE, LAND CSG, ND BOPS, SIWFWE
5	08/18/2014		LOG 4.5" CSG TOC @ 730', TIH W/ 1.66", POOH SD 1.66", WE HAD TO CHIZEL CMT OUT OF EVERY JT, TIH W/ 2-3/8" AND RET HEAD
6	08/19/2014		KICK LOOSE RBP, POOH W/ RBP, TIH W/ PROD, TAG FILL, CO FILL, POOH, LAND PROD TBG, TEST WELLHEAD TO 5K, RDMOSU
7	08/20/2014		POOH, LAND PROD TBG, TEST WELLHEAD TO 5K, RDMOSU