

FORM
6

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400680811			
Date Received:			

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set. A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: <u>100322</u>	Contact Name: <u>Erich Zwaagstra</u>
Name of Operator: <u>NOBLE ENERGY INC</u>	Phone: <u>(970) 371-7884</u>
Address: <u>1625 BROADWAY STE 2200</u>	Fax: _____
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>	Email: <u>ezwaagstra@nobleenergyinc.com</u>

For "Intent" 24 hour notice required, Name: _____ Tel: _____
COGCC contact: Email: _____

API Number <u>05-123-36701-00</u>	Well Number: <u>11-63-1HNL</u>
Well Name: <u>SHABLE USX PC AB</u>	
Location: QtrQtr: <u>SWSW</u> Section: <u>11</u> Township: <u>7N</u> Range: <u>64W</u> Meridian: <u>6</u>	
County: <u>WELD</u>	Federal, Indian or State Lease Number: _____
Field Name: <u>WATTENBERG</u>	Field Number: <u>90750</u>

Notice of Intent to Abandon Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.582369 Longitude: -104.525200

GPS Data:
 Date of Measurement: 11/06/2013 PDOP Reading: 2.1 GPS Instrument Operator's Name: william Baldwin

Reason for Abandonment: Dry Production for Sub-economic Mechanical Problems
 Other _____

Casing to be pulled: Yes No Estimated Depth: _____

Fish in Hole: Yes No If yes, explain details below

Wellbore has Uncemented Casing leaks: Yes No If yes, explain details below

Details: _____

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
NIOBRARA	15757	16325	07/18/2014	B PLUG CEMENT TOP	7000
Total: 1 zone(s)					

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
CONDUCTOR	26	16	49.09	96	80	96	16	VISU
SURF	13+3/4	9+5/8	36.00	792	360	792	16	VISU
1ST	8+3/4	7	26.00	7,245	490	7,245	1,282	CBL
1ST LINER	6+1/8	4+1/2	11.6	16,389	0	0	0	

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 7000 with _____ sacks cmt on top. CIBP #2: Depth 950 with _____ sacks cmt on top.
 CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
 CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 100 sks cmt from 7000 ft. to 5528 ft. Plug Type: STUB PLUG Plug Tagged:
 Set 50 sks cmt from 2502 ft. to 2232 ft. Plug Type: CASING Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
(Cast Iron Cement Retainer Depth)
 Set 375 sacks half in. half out surface casing from 730 ft. to 50 ft. Plug Tagged:
 Set 25 sacks at surface
 Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: Yes No
 Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: 6970 ft. of 7 inch casing Plugging Date: 07/23/2014
 *Wireline Contractor: JW WL *Cementing Contractor: Magna Energy Services
 Type of Cement and Additives Used: Class G Neat 15.8#
 Flowline/Pipeline has been abandoned per Rule 1103 Yes No *ATTACH JOB SUMMARY

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Stephanie Dionne
 Title: Base Production Tech Date: _____ Email: sdionne@nobleenergyinc.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

Attachment Check List

Att Doc Num	Name
400680812	CEMENT JOB SUMMARY
400680813	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)