

Magna Energy Services, LLC
17509 County Road 14
Ft. Morgan, CO 80701
(970) 867-9007
Fax (970) 867-8374

Job Log

Date: 8/8/14
Operator: Noble Energy Inc.
Well Name: Faramir Farms 6-32
Legal Location: NWSW Sec 6 T3N R64W
API# 05-123-19254-00
Weld County

8/5/14: MIRU P&A equipment, Check PSI 500#/500#, Blow well down, Kill well w/ 80 bbls water, ND well head, NU B.O.P.'s, TOOH w/ Tbg, Recovered 215 jts Tbg @ 6756', SWI.

8/6/14: RU Vaughn WL, Gyro well 6900', RD Vaughn WL, RU Nabors WL, RIH w/ CIBP w/ 2 sxs cement @ 6754', TIH w/ 75 stands Tbg @ 4805', establish circulation w/ 63 bbls water, Mix & pump 50 sxs of 15.8# Class G cement, displaced w/ 15 bbls water, TOOH w/ Tbg, ND B.O.P.'s, Unland Csg, NU B.O.P.'s, work Csg, No stretch, SWI.

8/7/14: RU Nabors WL, RIH, Tag TOC @ 3927', Run CBL, RD Nabors WL, Reland Csg, TIH w/ 39 stands Tbg @ 2509', establish circulation, Mix & pump 20 sxs of 15.8# Class G cement, displaced w/ 7 bbls water, TOOH w/ Tbg @ 738', establish circulation, Mix & pump 50 sxs of 15.8# Class G Cement to surface, LD 23 Jts TBG, SWI. Flush flow line w/ 15 bbls water.

8/8/14: Tag TOC @ 60' from surface, Top off well w/ 5 sxs of 15.8# Class G Cement to surface, RD P&A equipment, Dig well & flow line up, Cut & cap 6' below ground surface, Backfill, P&A complete.

*** All cement used is Class "G" Neat 15.8 # ***

Cementing Contractor: Magna Energy Services, LLC
Cementing Contractor Supervisor: Scott Marez
Operator Supervisor: Kelley Reinhardt
COGCC Representative: John Montoya
Wireline Contractor: Nabors WL, Vaughn WL



FIELD TICKET No. 2703
DELIVERED FROM _____
DATE 8-7-14

[illegible]

Wright, Howard

X

CUSTOMER REPRESENTATIVE

NAB0997 (09/12) • GMG Services, Inc. • 713 460-8801

White - Customer

Green - Customer

Canary - Accounting

Pink – Invoice

Gold - Field