

# Kwikturn Services, Inc.

Consulting • Service Tools

<b>Company</b> RED RIVER RANCH					<b>Lease</b>		
					<b>Well #</b> RRR 18-3E		
<b>Customer's Rep.</b>							
<b>PLUG DEPTH</b>	661						
<b>SACKS PUMPED</b>	2						
<b>PLUG DEPTH</b>	252						
<b>SACKS PUMPED</b>	16						
<b>TOTAL SACKS PUMPED</b>	23						

## Daily Summary

8/14/14

New crew from Greeley arrived at ten, MIRU and remove drive head and pull rods, unload and set up new, different tongs, trouble making hoses fit but finally got it to work. Sent water truck and cementer home, C/O and pull tubing, standing back 22 and laid the rest down. SDFN

8/15/14

Warm up rig and TIH with first plug, set at 661', TOOHSB 9 jts and laid rest down, pick up bailer and TIH and spot 2 sks cement on top of plug, TOOHSB and lay bailer down. TIH with second plug and set at 252', drop one jt and pump 16 sks cement on top of plug, pull up above cement and load hole with water. RD and move to the 2-1 location.

8/20/14

S&S Lopez dug out well head

8/21/14

Topar welding cut off well head 4' below ground level

Ran in 50' with 1" poly pipe and topped off casing with 4 sks cement and 1 in annulus.

8/22/14

Took Topar welder to location and welded 8 5/8 cap on top of casing, put well number, date, and RRR on cap. .Will backfill at later date.

**EASTERN COLORADO WELL SERVICE, LLC**

P.O. Box 244  
CHEYENNE WELLS, CO 80810  
Office: (719) 767-5100 Fax: (719) 767-5228

**Miscellaneous Equipment Rentals****DAILY TIME TICKET 1399 89**

Ticket Status: Submitted and Approved

Date 8/15/2014

Customer: Kwik Turn

WELL/LEASE R R R 18-3 E

State: CO County: Las Animas

**Remarks:**

Drove to location with two plugs and 18 sacks of cement. TIH with first plug o 661' set plug TOH with tbg. Ran in with dump bailer, dump two sacks of cement on top of CIBP, ran out with bailer. TIH with second plug set it at 252' , pump 16 sacks of cement TOOH laying down SDFN

Rental Equipment*		
Equipment	Required	Fee
Pump	<input type="checkbox"/>	\$0.00
BOP	<input type="checkbox"/>	\$0.00
Tank	<input type="checkbox"/>	\$0.00
Power Swivel	<input type="checkbox"/>	\$0.00

Large Rental Equipment Total: \$0.00

**EST. SUB TOTAL: 4,180.00**


Supplies and Materials Required*				
Supply/Material	Description/Size	Price Each	Qty	Extended Price
Mechanical Bridge Plug	5.5"	\$1,100.00	2	\$2,200.00
Grout Pump & Bailer	500 psi	\$1,350.00	1	\$1,350.00
Cement	Type I II	\$35.00	18	\$630.00

Current Supplies and Materials Total: \$4,180.00

\* Only Noted supplies required are displayed on the ticket, Equipment usage is noted by a check box in the required field

**Labor Information**

As part of our ongoing safety commitment, you are required to digitally sign your name stating you have successfully completed this work day safely and without an accident and that the ticket information is accurate

Title:	Employee Name:	Hours:	Date/Time of Digital Signature:	Customer Comments And Signatures:
Required Crew 1:	JAMES VALDEZ	0	8/18/2014 7:56:51 AM	
Required Crew 2:		0		
Required Crew 3:		0		
Required Crew 4:		0		
Required Crew 5:		0		
Required Crew 6:	JAMES VALDEZ	0	8/18/2014 7:56:54 AM	

Eastern Colorado Well Service LLC Approval: JAMES VALDEZ

8/25/2014 2:02:54 PM

Print Date: 8/25/2014 2:03:57 PM

**1399 89**