

Kwikturn Services, Inc.

Consulting • Service Tools

Company RED RIVER RANCH					Lease		
					Well # 14-1		
Customer's Rep.							
PLUG DEPTH	885						
SACKS PUMPED	2						
PLUG DEPTH	256						
SACKS PUMPED	16						
TOTAL SACKS PUMPED	32						

Daily Summary

6/12/14
 MIRU and spot in pipe trailer, TIH with plug and set at 885', TIH with bailer and spot 2 sks cement on plug, lay down bailer and TIH with plug and set at 256', TOOH and remove setting tool, TIH to just above plug and pump 16 sks cement on plug, pull up above cement and load hole. John Duran witnessed job and tested cement. (15.3 lbs)

6/13/14
 S&S Lopez dug out well head

7/18/14
 Topar welding cut off well head 4' below ground level

7/24/14
 Ran in 50' with 1" poly pipe and topped off well with cement, 6 sks in casing and 8 in annulus.

7/25/14
 Took Topar welder to location and welded 8 5/8 cap on top of casing, put well number, date, and RRR on cap. .Will backfill at later date.

EASTERN COLORADO WELL SERVICE, LLC

P.O. Box 244
CHEYENNE WELLS, CO 80610
Office: (719) 767-5100 Fax: (719) 767-5228

Miscellaneous Equipment Rentals

DAILY TIME TICKET 1399_54

Ticket Status: Submitted and Approved

Date 6/12/2014

Customer: Kwik Turn

WELL/LEASE RRR 14-1

State: CO County: Las Animas

Remarks:

Drove to location with two CIBP's and 18 sacks of cement. TIH with first plug and set it at 885' TOOH ran in with wire line dump bailer. Dump two sacks of cement on top of CIBP ran out with bailer TIH with second plug and set it at 256'. Pump 16 sacks of cement TOOH laid all out SDFN

Rental Equipment*		
Equipment	Required	Fee
Pump	<input type="checkbox"/>	\$0.00
BOP	<input type="checkbox"/>	\$0.00
Tank	<input type="checkbox"/>	\$0.00
Power Swivel	<input type="checkbox"/>	\$0.00

Large Rental Equipment Total: \$0.00

EST. SUB TOTAL: 4,180.00


Supplies and Materials Required*				
Supply/Material	Description/Size	Price Each	Qty	Extended Price
Mechanical Bridge Plug	5.5"	\$1,100.00	2	\$2,200.00
Grout Pump	500 psi	\$1,350.00	1	\$1,350.00
Cement	Type I II	\$35.00	18	\$630.00

Current Supplies and Materials Total: \$4,180.00

* Only Noted supplies required are displayed on the ticket, Equipment usage is noted by a check box in the required field

Labor Information

As part of our ongoing safety commitment, you are required to digitally sign your name stating you have successfully completed this work day safely and without an accident and that the ticket information is accurate

Title:	Employee Name:	Hours:	Date/Time of Digital Signature:	Customer Comments And Signatures:
Required Crew 1:	JAMES VALDEZ	0	6/19/2014 10:30:30 AM	
Required Crew 2:		0		
Required Crew 3:		0		
Required Crew 4:		0		
Required Crew 5:		0		
Required Crew 6:	JAMES VALDEZ	0	6/19/2014 10:30:32 AM	

Eastern Colorado Well Service LLC Approval: JAMES VALDEZ

6/19/2014 10:44:09 AM

Print Date: 6/19/2014 10:45:06 AM

1399_54