

# WELLBORE DIAGRAM

Swan 21-44

Directions:

API#: 05-121-11027

Lat. 39.860475

Long. -103.653979

Updated

Adams County CO

G.L.=

K.B.=

0

8 jts of 8-5/8" 24# set at 270'  
Cmt'd w/ sx to Surf.

TOC: 4030'

<<

>>

J Sand: 5148-5150 3/26/2014 DST at ~5145-5155'

<<

>>

J Sand: 5157-5161 3/13/2014

<<

>>

J Sand: 5228-5232 3/10/2014

<<

>>

J Sand: 5246-5259 1/2/2014

Ran 127 Jts of 5.5" 15.5# Csg. Landed at 5314'  
Cemented 200sx of 14.5# Cement. 1.39 Yield.

PBTD=

TD MD= 5325'

TD VD= 5325'