

WPX ENERGY ROCKY MOUNTAIN, LLC

KP 431-9

Kokopelli

SHL 2313' FNL 2158' FEL (9 6S 91W) BHL 826' FNL 1564' FEL (Section 9-T6S-R91W)

Section 9 T6S-R91W

Garfield County Colorado

Formation Tops

(Measured Depths)

Mesaverde @ 1974'

Top of Gas @ 3351'

Cameo @ 5626'

Rollins @ 5898'

PBTD @ 6136.8'

TMD @ 6185'

TVD @ 5645.6'

Conductor 26" Hole 18" casing/liner 60' W/22.5 Sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9-5/8" 32.3 ppf Csg. Set @ 1439.9'

In 13-1/2" Hole W/365 Sks. Cmt

Top Of Cement @ 3026'

Max Estimated Top Perf @ 3737'

5-1/2", 17 ppf. Csg. Set @6164.7' W/1327 Sks Cmt