

FORM  
2

Rev  
08/13

## State of Colorado

### Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400634997

#### APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

06/27/2014

Well Name: Franson

Well Number: 23-33 4N47W

Name of Operator: AUGUSTUS ENERGY RESOURCES LLC

COGCC Operator Number: 10489

Address: 36695 HWY 385

City: WRAY State: CO Zip: 80758

Contact Name: Loni Davis

Phone: (970)332-3585

Fax: (970)332-3587

Email: ldavis@augustusenergy.com

#### RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20130106

#### WELL LOCATION INFORMATION

QtrQtr: NESW Sec: 33 Twp: 4N Rng: 47W Meridian: 6

Latitude: 40.269840

Longitude: -102.635340

Footage at Surface: 2230 feet FNL/FSL FSL 1985 feet FEL/FWL FWL

Field Name: BUFFALO GRASS

Field Number: 7781

Ground Elevation: 4010

County: YUMA

GPS Data:

Date of Measurement: 06/13/2014 PDOP Reading: 1.5 Instrument Operator's Name: Darren Veal

If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

#### LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:



## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

4N/47W Sec 33: SW/4

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 386 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 1985 Feet

Above Ground Utility: 2018 Feet

Railroad: 5280 Feet

Property Line: 669 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 1044 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary \_\_\_\_\_ Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

Setbacks by Rule 318.B.

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

## DRILLING PROGRAM

Proposed Total Measured Depth: 2997 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 261 Feet (Including plugged wells)

Will a closed-loop drilling system be used? No

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No



Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: UIC Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Drilling pit

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	9+7/8	7	17	0	400	220	400	0
1ST	6+1/4	4+1/2	10.5	0	2997	100	2997	0

☒ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments



This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Loni Davis

Title: Oper. Acctg & Reg Spec Date: 6/27/2014 Email: ldavis@augustusenergy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 9/14/2014  
Expiration Date: 09/13/2016

**API NUMBER**

05 125 12122 00

### **Conditions Of Approval**

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

**COA Type**

**Description**

	<ol style="list-style-type: none"><li>1) Provide 48 hour notice prior to spud via electronic Form 42.</li><li>2) Note increased surface casing setting depth. Set at least 400' of surface casing due to WW depths. Setting depth must also be least 50' into Pierre Shale. Cement to surface.</li><li>3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.</li><li>4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole &amp; 5 sks cement in mouse hole.</li><li>5) Supply mud report showing chlorides, representative of conditions at TD, with Form 5.</li></ol>
	Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.



## **Best Management Practices**

<b>No</b>	<b><u>BMP/COA Type</u></b>	<b><u>Description</u></b>
1	Drilling/Completion Operations	<p>Best Management Practices Northern Yuma County, Colorado</p> <p>To address construction during drilling and all other operations associated with Oil and Gas development throughout Northern Yuma County, Colorado area StormWater Management Plans(SWMP) are in place and in compliance with the Colorado Department of Health and Environment (CDPHE) under Permit # COR-039921.</p> <p>Best Management Practices (BMP's) will be reviewed and maintained prior to, during and after construction of drilling site, laying of flowlines, installation of surface equipment and reclamation of site. Each location's BMP's will vary according to terrain and phase of construction and will be implemented in accordance to SWMP.</p> <p>Regular location inspections will be performed and any BMP's not effectively working will be documented and resolved in a timely manner.</p> <p>Spill Prevention, Control and Countermeasures will be implemented. Should any spills occur they will be cleaned up immediately and effectively to minimize any integration with storm water runoff. General good housekeeping practices will be performed to keep spills at a minimum.</p>

Total: 1 comment(s)

## **Applicable Policies and Notices to Operators**

Notice Concerning Operating Requirements for Wildlife Protection.

## **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
400634997	FORM 2 SUBMITTED
400635048	30 DAY NOTICE LETTER
400635049	WELL LOCATION PLAT
400635054	TOPO MAP
400635059	SURFACE AGRMT/SURETY
400635060	PROPOSED BMPs

Total Attach: 6 Files

## **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Final review completed; no LGD or public comment received.	9/9/2014 7:13:59 AM
Permit	Passed completeness.	6/30/2014 2:06:41 PM

Total: 2 comment(s)