

Document Number:
400682675

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 96850 4. Contact Name: GINA RANDOLPH
 2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC Phone: (303) 260-4509
 3. Address: 1001 17TH STREET - SUITE #1200 Fax: (303) 629-8268
 City: DENVER State: CO Zip: 80202

5. API Number 05-045-21791-00 6. County: GARFIELD
 7. Well Name: Federal Well Number: NER 343-32
 8. Location: QtrQtr: Lot 2 Section: 5 Township: 7S Range: 93W Meridian: 6
 Footage at surface: Distance: 139 feet Direction: FNL Distance: 2589 feet Direction: FWL
 As Drilled Latitude: 39.474976 As Drilled Longitude: -107.798853

GPS Data:
Date of Measurement: 07/03/2013 PDOP Reading: 1.9 GPS Instrument Operator's Name: J. KIRKPATRICK

** If directional footage at Top of Prod. Zone Dist.: 1963 feet. Direction: FSL Dist.: 639 feet. Direction: FEL
 Sec: 32 Twp: 6S Rng: 93W
 ** If directional footage at Bottom Hole Dist.: 1923 feet. Direction: FSL Dist.: 657 feet. Direction: FEL
 Sec: 32 Twp: 6S Rng: 93W

9. Field Name: RULISON 10. Field Number: 75400
 11. Federal, Indian or State Lease Number: COC41916

12. Spud Date: (when the 1st bit hit the dirt) 06/19/2014 13. Date TD: 06/28/2014 14. Date Casing Set or D&A: 06/28/2014

15. Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 10746 TVD** 10121 17 Plug Back Total Depth MD 10658 TVD** 10034

18. Elevations GR 7603 KB 7629
 One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:
RPM CBL MUDLOGS

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	42	16	0	42	VISU
SURF	13+1/2	9+5/8	32.3	0	1,177	300	0	1,177	VISU
1ST	8+3/4	4+1/2	11.6	0	10,726	1,050	6,152	10,726	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	3,952		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	6,795		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	9,750		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	10,601		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: The "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: GINA RANDOLPH

Title: PERMIT TECH II

Date:

Email: GINA.RANDOLPH@WPXENERGY.COM

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400682738	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400682741	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
400682705	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400682714	PDF-PULSED NEUTRON	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400682725	LAS-PULSED NEUTRON	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400682731	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400682733	LAS-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400682746	WELLBORE DIAGRAM	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400682747	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)