

BEREN CORP (CO) Williams #2

(3197801)

Workover

Page 1

Date of last WO:

PUR or UZ:

Objective: Plug and abandon well

BWO:

cc:

Final report cc: Adam, Paula W, Well File

8/21/14	Spot in Yetter Rig #9. SD
8/22/14	Lay down rods and tbg. SD
8/25/14	Set CIBP @ 4460', dump bail 2 sks cement on top of plug. Found free point at 1017'. Shoot off casing and pull 33 jts 4½" csg. TIH w/tbg to csg stub, pump 40 sks cement f/1020' to 920'. Pull tbg to 350', pump 50 sks ½ in ½ out of bottom of surface casing. TOH. SD
8/26/14	TIH w/ tubing, tag shoe plug 238' FS. Pump 15 sks at top of surface csg. RDMO.

FINAL REPORT