

Date of last WO:

PUR or UZ:

Objective: Plug and abandon well

BWO:

cc:

Final report cc: Adam, Paula W, Well File

8/29/14	MIRU Yetter Rig #9. Set CIBP @ 6720'. Dump bail 2 sks cmt on top of CIBP. SD
9/2/14	Found free point at 1000'. Recovered 24 jts 4.5" casing. TIH w/ tubing to csg stub at 1000', pump 40 sks cement, WOC. Pull tbg to 400', pump 50 sks ½ in ½ out of bottom of surface casing. TOH. SD
9/3/14	TIH w/ tubing, tag shoe plug 370' FS. Pump 25 sks, WOC. Tag plug @ 287' FS. Pump additional 15 sks and finish fill surface scg all the way to surface. RDMO
9/4/14	Weld plate on top of csg. Clean location

FINAL REPORT