

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400631569

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

Date Received:

07/03/2014

TYPE OF WELL OIL GAS COALBED OTHER _____

Refilling

ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Sidetrack

Well Name: Ochsner

Well Number: 5K-221

Name of Operator: PDC ENERGY INC

COGCC Operator Number: 69175

Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO

Zip: 80203

Contact Name: Shaye Marshall

Phone: (303)318-6131 Fax: ()

Email: shayelyn.marshall@pdce.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20090078

WELL LOCATION INFORMATION

QtrQtr: Lot 1 Sec: 5 Twp: 6N Rng: 67W Meridian: 6

Latitude: 40.516560

Longitude: -104.918050

Footage at Surface: 2355 feet ^{FNL/FSL} FNL 2433 feet ^{FEL/FWL} FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4883

County: WELD

GPS Data:

Date of Measurement: 05/30/2012 PDOP Reading: 2.4 Instrument Operator's Name: Adam Kelly

If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: ^{FNL/FSL} 2100 ^{FEL/FWL} FNL 1960 ^{FNL} FWL 500 ^{FEL/FWL} FNL 1960 ^{FEL/FWL} FWL
Sec: 5 Twp: 6N Rng: 67W Sec: 32 Twp: 7N Rng: 67W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: Fee State Federal Indian

The Surface Owner is: is the mineral owner beneath the location.

(check all that apply) is committed to an Oil and Gas Lease.

has signed the Oil and Gas Lease.

is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: Fee State Federal Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

NW/4 of Section 5 T6N R67W, W2 of Section 32 T7N R67W

Total Acres in Described Lease: 464 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1370 Feet

Building Unit: 1370 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 1984 Feet

Above Ground Utility: 2015 Feet

Railroad: 5280 Feet

Property Line: 200 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit

- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.

- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 630 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 500 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

E2W2 of Sec 32 T7N R67W and NENW of Sec 5 T6N R67W

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		240	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 14133 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 437 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

Drill cuttings will be land applied at PDC spread fields with COGCC Facility ID 425112, 429629, 430649, 431183, or 434889.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: 42511 or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+3/4	9+5/8	36	0	875	730	875	0
1ST	8+3/4	7	26	0	7375	650	7375	500
1ST LINER	6+1/8	4+1/2	13.5	6175	14133			

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments I certify that all conditions in the original permit are the same except the casing program. The surface hole size will now be 13 3/4 instead of 12 1/4. 7" casing string will be cemented to at least 200' above Niobrara, around 500' from surface. CBL will only be run in the vertical section of the wellbore. Distance to nearest well, Ochsner 5K-401, is 437'. 317.o. Exception Waiver attached.

I certify the following: The pad has been built. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). The location is not within a wildlife Restricted Surface Occupancy Area. No Form 2A required. There have been no changes to the location, land use or lease description. There will be no extra surface disturbance, so therefore no Form 2A is needed. The pit on the location (FacId 432215) is a closed pit and the surface has been reclaimed.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 430370

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Shaye Marshall

Title: Regulatory Analyst Date: 7/3/2014 Email: shayelyn.marshall@pdce.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: *Matthew Lee* Director of COGCC Date: 9/21/2014

Expiration Date: 09/20/2016

API NUMBER
05 123 36145 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Best Management Practices

<u>No BMP/COA Type</u>	<u>Description</u>

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400631569	FORM 2 SUBMITTED
400636613	OPEN HOLE LOGGING EXCEPTION
400638272	OFFSET WELL EVALUATION

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	<p>Requested bottom hole location be addressed as it doesn't match the previous APD or plat. Updated the nearest permitted or existing wellbore to 437 per OWE and map for the Drilling and Waste Plans tab.</p> <p>Operator requested the following to be added since the Location was already built: There have been no changes to the location. I certify that there has been no changes on land use, lease description. The pad has been built. The pit on the location has been closed and reclaimed. There will be no additional surface disturbance. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). The location is not within a wildlife Restricted Surface Occupancy Area. No Form 2A required.</p>	3/8/2014 3:15:58 PM
Engineer	Evaluated offset wells.	7/21/2014 9:43:13 AM
Permit	Corrected cultural distances as per opr.	7/17/2014 8:23:54 AM
LGD	<p>Please be advised that the subject property is located within the Town's Growth Management Area (GMA).The Town's Comprehensive Plan states, "The GMA is intended to define those specific areas within the planning area where it is most logical to extend urban services in the near term, that is, within the next five to ten years."</p> <p>Below please find the conditions of approval that are typically applied to conditional use grants for oil and gas operations located within Town.Therefore, the Town recommends the following conditions be placed on the subject oil and gas facilities:</p> <p>CONDITIONS:</p> <p>1.Prior to the commencement of drilling, the applicant shall submit comprehensive "Drilling and Site Improvement Plans" for review and approval by the Town.Such plans shall address initial drilling activities, initial installation of site improvements and details, and on-going perpetual maintenance of the subject site including, but not limited to, the following:</p> <p>a.Site access plan.The Drilling and Site Improvement Plans and supplemental information shall address site access points and haul routes for review and approval.</p> <p>b.Public street clean-up and tracking prevention.The Drilling and Site Improvement Plans and supplemental information shall include a tracking pad for review and approval.</p> <p>c.Site grading.The Drilling and Site Improvement Plans and supplemental information shall address site grading, including any earth berms for emergency containment.</p> <p>d.Site lighting.The Drilling and Site Improvement Plans and supplemental information shall include details regarding site lighting fixtures and locations.Security and other site lighting shall utilize full cutoff light fixtures to mitigate light pollution.</p> <p>e.Temporary screening. The applicant shall install a buffer to screen the initial drilling activities and installation of site improvements from surrounding</p>	7/8/2014 11:02:50 AM

neighborhoods and streets. The temporary buffer shall include hay bales to enclose the drilling operations to provide noise mitigation.

f. Permanent screening. Given the close proximity to residential neighbors, the Drilling and Site Improvement Plans shall depict proposed long-term screening materials including landscaping, earth berms and any other screening methods to mitigate visual impacts.

g. Fencing. The Drilling and Site Improvement Plans shall depict fencing of the perimeter of the site. Fencing materials shall be reviewed for approval by the Town based upon the character of the surrounding neighborhood.

h. Oil and gas equipment.

(1) The applicant shall utilize electric motors in order to mitigate the noise impacts to the neighboring properties.

(2) The applicant shall ensure that the wells and tanks are of the minimum size required to satisfy present and future functional requirements to mitigate visual impacts.

(3) Low profile tanks shall be utilized and shall be installed in the least visible manner possible.

(4) All tanks and equipment shall be painted to blend-in with the surrounding landscape.

i. Air quality.

(1) The applicant shall participate in any required Environmental Protection Agency (EPA) air quality monitoring and/or testing by allowing EPA to install equipment on site for said monitoring and testing.

(2) The applicant shall install and operate an emissions control device (ECD) capable of reducing Volatile Organic Compound (VOC) emissions on the subject oil and gas equipment in accordance with Colorado Oil and Gas Conservation Commission (COGCC) and/or the Colorado Department of Public Health and Environment (CDPHE) rules and regulations.

(3) The applicant shall submit to the Town copies of all air emissions reporting as required by the COGCC and/or the CDPHE's Air Pollution Control Division.

j. Water quality.

(1) The applicant shall ensure that any hydrocarbon discharges from the site comply with all state and federal water quality requirements.

(2) The applicant shall provide test results from Groundwater Baseline Sampling and Monitoring required by COGCC Rule 318A.e(4) to the Town. (condition updated 10/28/13 to reflect updated COGCC rule)

k. Emergency containment. The secondary containment berm surrounding all storage vessels shall be designed and constructed to contain a minimum of 110% of the volume of the largest vessel located within the containment area or to State of Colorado standards, whichever requirements are more stringent.

l. Waste disposal. The applicant shall submit to the Town copies of all waste management reports as required by the COGCC and/or the CDPHE rules and regulations.

m. The following certification blocks shall be included on the Drilling and Site Improvement Plans:

(1) A signed owner's acknowledgement certification block.

	<p>(2)A signed drilling operator's acknowledgement certification block.</p> <p>n.The following notes shall be included on the Drilling and Site Improvement Plans:</p> <p>(1)The applicant shall comply with all rules and regulations of the Colorado Oil and Gas Conservation Commission (COGCC).</p> <p>(2)The applicant shall comply with all rules and regulations of the Colorado Department of Public Health and Environment (CDPHE).</p> <p>(3)The applicant shall maintain on-going compliance with all conditions of the Town and Windsor-Severance Fire Rescue.</p> <p>(4)The facilities shall be kept clean and otherwise properly maintained at all times.</p> <p>(5)The existing access may be utilized for oil and gas well activities.This access point is temporary and will be required to be removed at such time that permanent access is available in the future.</p> <p>2.The applicant shall address and comply with the conditions of Windsor-Severance Fire Rescue.</p> <p>ACCESS COMMENTS:</p> <p>If access to the site is proposed from a Town of Windsor street, such access point (s) shall require approval from the Town of Windsor Engineering Department and any required access improvements, street clean-up, tracking pads, etc., shall be addressed accordingly.</p>		
Permit	Passed completeness.	7/3/2014 2:38:07	PM

Total: 5 comment(s)