

Nebraska Drillers Inc.

Well : RUHL #1
Field : Wattenberg
County : Weld County **State** : Colorado
Surface : Lat: 40.1257900 Long: -104.5771000
: 1980 FSL, 1950 FEL, SENW Sec 20 T2N R64W
API # : 05-123-05071
Grd Elev : 4992' GR **KB Elevation:** 4999' KB

Log Tops:

Fox Hills Base 905'
 Sussex ?
 Niobrara 6825'
 Codell ?
 J Sand 7502'

Surface Casing

10-3/4" Surface Casing set
 @ 199', cmt'd w/ 175 sx

Production Hole

Unknown size

The diagram is a vertical well log. At the top, there is a shaded rectangular area representing the '5 sxs cmt Surface Plug'. Below this is a large section of the wellbore, mostly defined by a dashed line, representing the '10 sxs cmt from 176-200'' casing. Further down, there is another shaded rectangular area representing the '20 sxs cmt from 7494-7550'' casing. The bottom of the well is marked with a solid line and labeled 'TD 7638''.

5 sxs cmt Surface Plug

10 sxs cmt from 176-200'

20 sxs cmt from 7494-7550'

TD 7638'

Well History:

Spud 05/11/1955
 P&A'ed 05/27/1955

Drawn by:

Scott Reed

Date:

08/26/2014