

FORM 5A

Rev 06/12

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Table with columns DE, ET, OE, ES

Document Number: 400675562

Date Received: 09/03/2014

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10489
2. Name of Operator: AUGUSTUS ENERGY RESOURCES LLC
3. Address: 36695 HWY 385
City: WRAY State: CO Zip: 80758
4. Contact Name: Loni Davis
Phone: (970) 332-3585
Fax: (970) 332-3587
Email: ldavis@augustusenergy.com

5. API Number 05-125-12106-00
6. County: YUMA
7. Well Name: McCall
Well Number: 43-09 1N46W
8. Location: QtrQtr: NESE Section: 9 Township: 1N Range: 46W Meridian: 6
9. Field Name: SCHRAMM Field Code: 76825

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 09/02/2014 End Date: 09/02/2014 Date of First Production this formation: 09/02/2014
Perforations Top: 2504 Bottom: 2524 No. Holes: 40 Hole size: 47/100

Provide a brief summary of the formation treatment: Open Hole: []

Total usage of 50,040 16/30 Texas Gold sand 50,000# 12/20 Texas Gold sand, & 560,000 scf N2 w/ 2 cooldowns

This formation is commingled with another formation: [] Yes [X] No

Total fluid used in treatment (bbl): 352 Max pressure during treatment (psi): 1831
Total gas used in treatment (mcf): 560 Fluid density at initial fracture (lbs/gal): 8.33
Type of gas used in treatment: NITROGEN Min frac gradient (psi/ft): 0.50
Total acid used in treatment (bbl): 12 Number of staged intervals: 6
Recycled water used in treatment (bbl): 0 Flowback volume recovered (bbl): 0
Fresh water used in treatment (bbl): 340 Disposition method for flowback:
Total proppant used (lbs): 100040 Rule 805 green completion techniques were utilized: [X]

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 09/02/2014 Hours: 3 Bbl oil: 0 Mcf Gas: 67 Bbl H2O: 0
Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 0 Bbl H2O: 0 GOR: 0
Test Method: Flowing Casing PSI: 790 Tubing PSI: Choke Size: 6/64
Gas Disposition: SOLD Gas Type: DRY Btu Gas: 998 API Gravity Oil: 0
Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: [] Yes [] No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Loni J. Davis

Title: Oper Acctg & Reg Spec Date: 9/3/2014 Email ldavis@augustusenergy.com
:

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400675562	FORM 5A SUBMITTED
400678442	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)