

doc#2597098

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYSUBMIT IN TRIPL
(Other instructions
reverse side)Approved:
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

C-22506

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Federal

9. WELL NO.

3-1

10. FIELD AND POOL, OR WILDCAT

Shire Gulch

11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

Sec. 3-T10S-R97W, 6th F

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

5579' KB

12. COUNTY OR PARISH

MESA

13. STATE

COLO.

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

☐
☒
☐
☐

PULL OR ALTER CASING

☐
☐
☐
☐

FRACTURE TREAT

MULTIPLE COMPLETE

SHOOT OR ACIDIZE

ABANDON*

REPAIR WELL

CHANGE PLANS

(Other)

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

☐
☐
☐

REPAIRING WELL

☐
☐
☐

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

ALTERING CASING

ABANDONMENT*

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

1. Set G0 bridge plug at 2920 with wireline. Placed 5' cement plug at 2915' w/dump bailer.
2. Perforated 5½" csg with one 3/8" hole as follows: 2807, 2805, 2803, 2753, 2750, 2748.
3. Foam sand-frac perforated intervals (Cozette) w/14,000# 100 mesh sand, 50,000# 20-40 mesh sand, 300 Bbls frac fluid, and 658,000 SCF nitrogen gas.
Job complete 2:30 P.M. March 5, 1980.
4. Flow testing well. Prep. to connect to gas sales line.

18. I hereby certify that the foregoing is true and correct

SIGNED

J. A. Muir

TITLE Engineer

DATE 4/15/80

(This space for Federal or State office use)

APPROVED BY

Pauline

FOR

E. W. GUYNN
DISTRICT ENGINEER

DATE

APR 21 1980

CONDITIONS OF APPROVAL, IF ANY:

Accepted

*See Instructions on Reverse Side

open