



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

269116

TICKET NUMBER 47000

LOCATION Oakley KS

FOREMAN Dane Retzlaff

FIELD TICKET & TREATMENT REPORT

CEMENT

60

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																
6-25-14	9160	Alpha Mula # 16	19	10	55	Lincoln																
CUSTOMER			<div> <div>Limer Co. RD a6 Gasplant</div> <table border="1"> <tr> <th>TRUCK #</th><th>DRIVER</th><th>TRUCK #</th><th>DRIVER</th></tr> <tr> <td>456</td><td>Mike</td><td></td><td></td></tr> <tr> <td>397</td><td>Jeff</td><td></td><td></td></tr> <tr> <td></td><td></td><td></td><td></td></tr> </table> </div>				TRUCK #	DRIVER	TRUCK #	DRIVER	456	Mike			397	Jeff						
TRUCK #	DRIVER	TRUCK #					DRIVER															
456	Mike																					
397	Jeff																					
MAILING ADDRESS																						
CITY																						
STATE																						
ZIP CODE																						

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>324</u>	CASING SIZE & WEIGHT <u>8 5/8 24 LBS</u>
CASING DEPTH <u>323.19</u>	DRILL PIPE <u>4</u>	TUBING <u>NA</u>	OTHER _____
SLURRY WEIGHT <u>14.8</u>	SLURRY VOL <u>1.36</u>	WATER gal/sk <u>6.7</u>	CEMENT LEFT in CASING <u>30</u>
DISPLACEMENT <u>18.67</u>	DISPLACEMENT PSI <u>150</u>	MIX PSI <u>100</u>	RATE <u>6 BBL per min.</u>

REMARKS: Jaffery meeting. Rig up. Run casing. mix 165 sks of Class A cement 3% Calcium Chloride. 2% Bentonite. Release plug. Displace 18 3/4 BBLs of water. Shut in. Wash pump and lines. Rig down. Cement did circulate to surface.

Thanks Dane + crew

[illegible]


Rayin 3737

AUTHORIZATION *Armando*

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

TICKET NUMBER 46643

LOCATION Chalton, MO

FOREMAN Miles Shaw

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-7-14	9160	Alpha Mule #16	19	10S	5SW	Lincoln
CUSTOMER <u>Wierking Fullerton</u>			Limon Co Sonoma Co to Rd 24 S to 95th Rd 10 into			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			4527UR	Jordan L		
			5ATW7	Steven O		
CITY	STATE	ZIP CODE				

JOB TYPE Long String HOLE SIZE 7 7/8" HOLE DEPTH POGS CASING SIZE & WEIGHT 5 3/4" 15 #
CASING DEPTH 8057' DRILL PIPE TUBING OTHER PCO 4810'
SLURRY WEIGHT 13.8 SLURRY VOL 1,42 WATER gal/sk CEMENT LEFT in CASING 42'
DISPLACEMENT 187 DISPLACEMENT PSI 1200 MIX PSI 1700 RATE

REMARKS: Safety meeting and rig up on Martin drilling rig 25 Float equipment
Turbolizer on 5th # 1, 2, 3, 4, 7, 14, 19, 20, 24, 25 Baskets on 5th # 3+ 78
Centralizer on 5th # 77, 79 Picked up top of 5th # 78 @ 480' Run 193 5th Circulate @ 5th # 100
Circulate casing 4 hrs. Pump mud flush mix 302 SAs Class A 108 gal 2.8 gal 15# Kolsal
down casing shut down Clear pump & lines release plug displace 187 bbls water with 1200 psi.
lift plug did land @ 1700 psi. plug held

Thanks Miles & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	3175. ⁰⁰	3175. ⁰⁰
5406	100	MILEAGE	5.25	525. ⁰⁰
5407A	15.1 Tons	Ton Mitepago delivery	1.75	2643. ⁰⁰
1110A	1610 #	Kolsal	.56	901.60
1111	1611 #	Salt	.50	805.50
1115A	322 SAs	Class A Cement	16.75	5393.50
1118B	605 #	Bentonite gel	.27	163.35
1144G	500 gal	mud flush	1.00	500. ⁰⁰
4104	2	5 1/2" Baskets	290. ⁰⁰	580. ⁰⁰
4130	2	5 3/4" Centralizer	61. ⁰⁰	122. ⁰⁰
4136	13	5 1/2" Turbolizers	75.75	984.75
4159	1	5 1/2" Float shoe API	433.75	433.75
4285	3	5 1/2" Port collar	2178.75	6536.25
4454	1	5 1/2" Latch down plug	567. ⁰⁰	567. ⁰⁰
Top of the port collars weren't charge on the last two pipe jobs			Subtotal	23330.70
The Alpha mule #4 and the MASA #12 X less 108 gal. cement			Subtotal	2333.00
			Subtotal	20997.63
			SALES TAX	116.25
			ESTIMATED TOTAL	22113.88

Ravin 3737

AUTHORIZATION Garry Smith

TITLE Co Man

DATE 8/7/14

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this for

