

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400668742

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

08/21/2014

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____Refiling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: DIAMOND VALLEY EAST

Well Number: 12

Name of Operator: EXTRACTION OIL & GAS LLC

COGCC Operator Number: 10459

Address: 1888 SHERMAN ST #200

City: DENVER State: CO Zip: 80203

Contact Name: Nick Curran

Phone: (720)420-5745

Fax: (720)420-5800

Email: nick.curran@iptenergyservices.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20130028

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 23 Twp: 6N Rng: 67W Meridian: 6

Latitude: 40.467880

Longitude: -104.869800

Footage at Surface: 976 feet FNL/FSL FSL 155 feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4769

County: WELD

GPS Data:

Date of Measurement: 08/19/2013 PDOP Reading: 1.9 Instrument Operator's Name: MARK ANGELL

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

 2475 FSL 460 FEL 2475 FSL 460 FWL
 Sec: 22 Twp: 6N Rng: 67W Sec: 21 Twp: 6N Rng: 67W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☐ is the mineral owner beneath the location.
(check all that apply) ☐ is committed to an Oil and Gas Lease.☐ has signed the Oil and Gas Lease.☒ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: applicant is owner

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T6N-R67W, SEC. 22: SW/4

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease #

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 155 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 950 Feet
Building Unit: 991 Feet
High Occupancy Building Unit: 3337 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 954 Feet
Above Ground Utility: 1305 Feet
Railroad: 1360 Feet
Property Line: 155 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government:

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 09/01/2013

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 519 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): Unit Number:

SPACING & FORMATIONS COMMENTS

S2/N2 & N2/S2 OF SEC. 21-T6N-R67W; S2/N2 & N2/S2 OF SEC. 22-T6N-R67W

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		640	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 17031 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 519 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	750	398	750	0
1ST	8+3/4	7	26	0	7565	727	7565	3000
1ST LINER	6+1/8	4+1/2	13.5	7545	17031			

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments 1.)THE ONLY BUILDING < 1000 FEET FROM PROPOSED LOCATION (950' SE) IS OWNED BY EXTRACTION O&G.
2.) Pad slot #12. This well is a Rule 318A.a.(4)D Horizontal GWA Well; PSU Map is attached. Operator notified via certified mail on 9/4/13 all owners as defined in C.R.S. 34-60-103(7) within the proposed spacing unit and received no written objections. Extraction respectfully requests that the Rule 318A.a.(4)D Horizontal well and proposed spacing unit be approved. Applicant is surface owner and waives Rule 318A.a & 318A.c. Request is attached.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 435083

Is this application being submitted with an Oil and Gas Location Assessment application? _____ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Nick Curran

Title: Regulatory Tech Date: 8/21/2014 Email: nick.curran@iptenergyservices.

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 9/25/2014

Expiration Date: 09/24/2016

API NUMBER

05 123 40318 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	Operator shall comply with Buffer Zone Move-In, Rig-Up Notice Policy dated 12-16-2013.
	Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	• Bradenhead Monitoring: Operator acknowledges and will comply with COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
2	Drilling/Completion Operations	Anti-Collision: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed wells. The anti-collision scan may include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, operators may have gyro surveys conducted to verify bottomhole location. The proposed well may only be drilled if the anti-collision review results indicate that the risk of collision is sufficiently low as defined by the anti-collision plan, with separation factors greater than 1.5, or if the risk of collision has been mitigated through other means including shutting in wells, plugging wells, increased drilling fluid in the event of lost returns or as is appropriate for the specific situation. In the event of an increased risk of collision, that risk will be mitigated to prevent harm to people, the environment or property. For the proposed well, upon conclusion of drilling operations, an as-constructed directional survey will be submitted to the COGCC with the Form 5.
3	Drilling/Completion Operations	Open hole resistivity log with gamma ray will be run on one of the first wells drilled on this pad to describe the stratigraphy of the vertical section of the wellbore and to adequately verify the setting depth of the surface casing and aquifer coverage. The Drilling Completion Report-Form 5 for every well on the pad shall identify which well was logged.

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
2167860	EXCEPTION LOC REQUEST
400668742	FORM 2 SUBMITTED
400668831	OffsetWellEvaluations Data
400668837	DIRECTIONAL DATA
400668922	WAIVERS
400668923	WAIVERS
400668928	ANTI-COLLISION WAIVER
400668931	WAIVERS
400669088	PROPOSED SPACING UNIT
400669612	WELL LOCATION PLAT
400671185	DEVIATED DRILLING PLAN
400671188	FORM 2 SUBMITTED
400671892	FORM 2 SUBMITTED

Total Attach: 13 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Objection by Weld RE-4 School District has been removed. Final review complete.	9/24/2014 8:23:56 AM

Permit	<p>An Objection was received on 9/8 from Weld RE-4 School District regarding DVE 12 & 13. The objection includes notifications and lease issues. Opr notified and form on hold.</p> <p>Attached Exception Loc request for 318A.a and 318A.c as per opr.</p>	<p>9/18/2014 7:14:02 AM</p>	
Engineer	<p>Evaluated offset wells.</p>	<p>9/9/2014 11:56:49 AM</p>	
LGD	<p>Please be advised that the subject property is located within the Town's Growth Management Area (GMA).The Town's Comprehensive Plan states, "The GMA is intended to define those specific areas within the planning area where it is most logical to extend urban services in the near term, that is, within the next five to ten years."</p> <p>Below please find the conditions of approval that are typically applied to conditional use grants for oil and gas operations located within Town.Therefore, the Town recommends the following conditions be placed on the subject oil and gas facilities:</p> <p>CONDITIONS:</p> <p>1.Prior to the commencement of drilling, the applicant shall submit comprehensive "Drilling and Site Improvement Plans" for review and approval by the Town.Such plans shall address initial drilling activities, initial installation of site improvements and details, and on-going perpetual maintenance of the subject site including, but not limited to, the following:</p> <p>a.Site access plan.The Drilling and Site Improvement Plans and supplemental information shall address site access points and haul routes for review and approval.</p> <p>b.Public street clean-up and tracking prevention.The Drilling and Site Improvement Plans and supplemental information shall include a tracking pad for review and approval.</p> <p>c.Site grading.The Drilling and Site Improvement Plans and supplemental information shall address site grading, including any earth berms for emergency containment.</p> <p>d.Site lighting.The Drilling and Site Improvement Plans and supplemental information shall include details regarding site lighting fixtures and locations.Security and other site lighting shall utilize full cutoff light fixtures to mitigate light pollution.</p> <p>e.Temporary screening. The applicant shall install a buffer to screen the initial drilling activities and installation of site improvements from surrounding neighborhoods and streets. The temporary buffer shall include hay bales to enclose the drilling operations to provide noise mitigation.</p> <p>f.Permanent screening. Given the close proximity to residential neighbors, the Drilling and Site Improvement Plans shall depict proposed long-term screening materials including landscaping, earth berms and any other screening methods to mitigate visual impacts.</p> <p>g.Fencing.The Drilling and Site Improvement Plans shall depict fencing of the perimeter of the site.Fencing materials shall be reviewed for approval by the Town based upon the character of the surrounding neighborhood.</p> <p>h.Oil and gas equipment.</p> <p>(1)The applicant shall utilize electric motors in order to mitigate the noise impacts to the neighboring properties.</p> <p>(2)The applicant shall ensure that the wells and tanks are of the minimum size required to satisfy present and future functional requirements to mitigate visual</p>	<p>8/27/2014 4:11:44 PM</p>	

	<p>impacts.</p> <p>(3)Low profile tanks shall be utilized and shall be installed in the least visible manner possible.</p> <p>(4)All tanks and equipment shall be painted to blend-in with the surrounding landscape.</p> <p>i.Air quality.</p> <p>(1)The applicant shall participate in any required Environmental Protection Agency (EPA) air quality monitoring and/or testing by allowing EPA to install equipment on site for said monitoring and testing.</p> <p>(2)The applicant shall install and operate an emissions control device (ECD) capable of reducing Volatile Organic Compound (VOC) emissions on the subject oil and gas equipment in accordance with Colorado Oil and Gas Conservation Commission (COGCC) and/or the Colorado Department of Public Health and Environment (CDPHE) rules and regulations.</p> <p>(3)The applicant shall submit to the Town copies of all air emissions reporting as required by the COGCC and/or the CDPHE's Air Pollution Control Division.</p> <p>j.Water quality.</p> <p>(1)The applicant shall ensure that any hydrocarbon discharges from the site comply with all state and federal water quality requirements.</p> <p>(2)The applicant shall provide test results from Groundwater Baseline Sampling and Monitoring required by COGCC Rule 318A.e(4) to the Town. (condition updated 10/28/13 to reflect updated COGCC rule)</p> <p>k.Emergency containment.The secondary containment berm surrounding all storage vessels shall be designed and constructed to contain a minimum of 110% of the volume of the largest vessel located within the containment area or to State of Colorado standards, whichever requirements are more stringent.</p> <p>l.Waste disposal.The applicant shall submit to the Town copies of all waste management reports as required by the COGCC and/or the CDPHE rules and regulations.</p> <p>m.The following certification blocks shall be included on the Drilling and Site Improvement Plans:</p> <p>(1)A signed owner's acknowledgement certification block.</p> <p>(2)A signed drilling operator's acknowledgement certification block.</p> <p>n.The following notes shall be included on the Drilling and Site Improvement Plans:</p> <p>(1)The applicant shall comply with all rules and regulations of the Colorado Oil and Gas Conservation Commission (COGCC).</p> <p>(2)The applicant shall comply with all rules and regulations of the Colorado Department of Public Health and Environment (CDPHE).</p> <p>(3)The applicant shall maintain on-going compliance with all conditions of the Town and Windsor-Severance Fire Rescue.</p> <p>(4)The facilities shall be kept clean and otherwise properly maintained at all times.</p> <p>(5)The existing access may be utilized for oil and gas well activities.This access point is temporary and will be required to be removed at such time that permanent access is available in the future.</p>		
--	--	--	--

	<p>2.The applicant shall address and comply with the conditions of Windsor-Severance Fire Rescue.</p> <p>ACCESS COMMENTS:</p> <p>If access to the site is proposed from a Town of Windsor street, such access point (s) shall require approval from the Town of Windsor Engineering Department and any required access improvements, street clean-up, tracking pads, etc., shall be addressed accordingly.</p>	
Permit	Passed completeness. Exception Location Request attached. Extraction is the surface owner and self-waives the out of window and twinning waivers in the 'comments' section.	8/25/2014 9:12:46 AM
Permit	<p>Return to draft. Exception letter request and waiver still missing.</p> <p>Deviated drilling plan attached.</p>	8/25/2014 8:51:04 AM
Permit	Returned to Draft: Deviated Drilling plan corrupted and not openable. Exception Request letter missing	8/22/2014 10:49:03 AM

Total: 7 comment(s)