

## WELLBORE DIAGRAM

Directions: Hwy 85 N to Hwy 392, W to Hwy 257, N to Rd 78, W to Rd 15, 1/4 mi N, W in

### Bayswater E & P Blehm 16-19

NESE Sec 19-T7N-R67W  
SHL: 1785' FSL, 503' FEL  
BHL: 684' FSL, 673' FEL  
Weld County CO  
05-123-37695

Updated  
2/13/2014  
SMS

G.L.= 4978  
K.B.= 4991  
13

8-5/8" 24# set at 793'  
Cmt'd w/ 300 sx to Surf.

TOC: 950 ft  
CBL 2/11/14

<<

>>

Codell 7178-7200 ft, 4 spf, 88 holes  
Frac Codell w/ 6906 BLWR & 191,582 lbs 30/50 white sand

PBTD= 7,260'

4 1/2", 11.6# LTC 7315' (7-7/8" O.H.)

TD MD= 7,325'

Cmt'd w/ 880 sx

TD VD= 7,138'

to