



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

270664

TICKET NUMBER 46713
LOCATION Oakley KS
FOREMAN Dane Petzloff

FIELD TICKET & TREATMENT REPORT CEMENT

620-431-9210 or 800-467-8676

CEMENT

55

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-20-14	5659	Scherler 1-10	10	17s	45w	Kiowa
CUSTOMER						
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
Mull			377	Mike		
CITY			460	Rob		
STATE		ZIP CODE		harry		

Chayeneul
East side
south to
RD 2
west to
dezelene
south to
Rig.

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>341.8</u>	CASING SIZE & WEIGHT <u>8 5/8</u>
CASING DEPTH <u>341</u>	DRILL PIPE <u>4.5</u>	TUBING _____	OTHER _____
SLURRY WEIGHT <u>14.8</u>	SLURRY VOL <u>1.36</u>	WATER gal/sk <u>6.5</u>	CEMENT LEFT in CASING <u>20</u>
DISPLACEMENT <u>20.44</u>	DISPLACEMENT PSI <u>200</u>	MIX PSI <u>50</u>	RATE <u>Mix 6 Displace 7</u>

DISPLACEMENT 20.49 DISPLACEMENT PSI 2433 MIX 2.5 225
REMARKS: Safety meeting. Rig up. Break circulation. mix 265 sks of Class A cement
2% cc 3% gel. Release plug. Displace 20.5. Wash pump + lines. Shut in.
Cement did circulate.

Play down at 8:00 pm

Thanks Dance DU crew

[illegible]

Revin 3737

AUTHORIZATION

TITLE

DATE _____

AUTHORIZATION John Wilson Date 1/25/2011

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.