

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400702100

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Eileen Roberts
Phone: (303) 2284330
Fax: (303) 2284286
Email: eroberts@nobleenergyinc.com

5. API Number 05-123-38653-00
6. County: WELD
7. Well Name: Wells Ranch
Well Number: AE30-66-1BHNB
8. Location: QtrQtr: NWSW Section: 29 Township: 6N Range: 62W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 07/07/2014 End Date: 07/10/2014 Date of First Production this formation: 08/23/2014

Perforations Top: 7034 Bottom: 11993 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

Frac'd the Niobrara w/ 6892582 gals of PermStim and Slick Water with 4648280#'s of Ottawa sand.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 164109 Max pressure during treatment (psi): 6315

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.92

Total acid used in treatment (bbl): 0 Number of staged intervals: 26

Recycled water used in treatment (bbl): 73096 Flowback volume recovered (bbl): 258

Fresh water used in treatment (bbl): 91012 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 4648280 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 09/01/2014 Hours: 24 Bbl oil: 159 Mcf Gas: 333 Bbl H2O: 402

Calculated 24 hour rate: Bbl oil: 159 Mcf Gas: 333 Bbl H2O: 402 GOR: 2094

Test Method: FLOWING Casing PSI: 914 Tubing PSI: 598 Choke Size: 20/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1345 API Gravity Oil: 66

Tubing Size: 2 + 7/8 Tubing Setting Depth: 6763 Tbg setting date: 08/13/2014 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Eileen Roberts _____

Title: Regulatory Specialist _____

Date: _____

Email: eroberts@nobleenergyinc.com _____

:

Attachment Check List

Att Doc Num

Name

400702100

FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)