



**DRILLING COMPANY, INC.**  
**WICHITA, KANSAS**

**Proposed Wellbore Configuration**

Date:	10/7/2014
Well Name:	NWAU #7
Location:	NE SW 25-T13S-R43W
County:	Cheyenne
State:	Colorado
API:	05-017-07036
KB:	3997'
GL:	3987'
Spud Date:	9/20/1989

Note: Original well name was the Klement #4. Original operator was UPRC.

2-7/8" tubing w/pump & rods

Calculated top of cement at 4100'

Peforations in Morrow at 5200'-5230' (120 holes)

5-1/2",15.5#,K55, ST&C csg set at 5330'  
Cmt w/100 sks. 50/50 Poxmix & 150 sks. Class A