

After Replug Schematic:

8-5/8 24# K55 Surface  
Set @ 206' MD

25 sx cement @ top of surface csg and backside  
of surface casing

50 sx balanced plug from 256' to 52'

75 sx balanced plug from 2500' to 2059'

7 7/8" OH  
To 6695' MD

