

FORM  
2A

Rev  
08/13

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400702651

Date Received:

10/10/2014

Oil and Gas Location Assessment

☒ New Location    ☐ Refile    ☐ Amend Existing Location    Location#: \_\_\_\_\_

Submit signed original form. This Oil and Gas Location Assessment is to be submitted to the COGCC for approval prior to any ground disturbance activity associated with oil and gas operations. Approval of this Oil and Gas Location Assessment will allow for the construction of the below specified Location; however, it does not supersede any land use rules applied by the local land use authority. Please see the COGCC website at <http://cogcc.state.co.us/> for all accompanying information pertinent this Oil and Gas Location Assessment.

Location ID:

Expiration Date:

☒ This location assessment is included as part of a permit application.

CONSULTATION

- ☐ This location is included in a Comprehensive Drilling Plan. CDP # \_\_\_\_\_
- ☐ This location is in a sensitive wildlife habitat area.
- ☐ This location is in a wildlife restricted surface occupancy area.
- ☐ This location includes a Rule 306.d.(1)A.ii. variance request.

Operator

Operator Number: 10373

Name: NGL WATER SOLUTIONS DJ LLC

Address: 3773 CHERRY CRK NORTH DR #1000

City: DENVER    State: CO    Zip: 80209

Contact Information

Name: Paul Gottlob

Phone: (720) 420-5747

Fax: ( )

email: paul.gottlob@iptenergyservices.com

RECLAMATION FINANCIAL ASSURANCE

☒ Plugging and Abandonment Bond Surety ID: 20110128    ☐ Gas Facility Surety ID: \_\_\_\_\_

☐ Waste Management Surety ID: \_\_\_\_\_

LOCATION IDENTIFICATION

Name: NGL    Number: C5

County: WELD

Quarter: SWSW    Section: 29    Township: 2N    Range: 64W    Meridian: 6    Ground Elevation: 4937

Define a single point as a location reference for the facility location. When the location is to be used as a well site then the point shall be a well location.

Footage at surface: 234 feet FSL from North or South section line

403 feet FWL from East or West section line

Latitude: 40.102970    Longitude: -104.582800

PDOP Reading: 2.2    Date of Measurement: 10/03/2014

Instrument Operator's Name: Bradley Laman

## RELATED REMOTE LOCATIONS

(Enter as many Related Locations as necessary. Enter the Form 2A document # only if there is no established COGCC Location ID#)

This proposed Oil and Gas Location is:

LOCATION ID #

FORM 2A DOC #

## FACILITIES

Indicate the number of each type of oil and gas facility planned on location

Wells	1	Oil Tanks*		Condensate Tanks*		Water Tanks*		Buried Produced Water Vaults*	
Drilling Pits		Production Pits*		Special Purpose Pits		Multi-Well Pits*		Modular Large Volume Tanks	
Pump Jacks		Separators*		Injection Pumps*		Cavity Pumps*		Gas Compressors*	
Gas or Diesel Motors*		Electric Motors		Electric Generators*		Fuel Tanks*		LACT Unit*	
Dehydrator Units*		Vapor Recovery Unit*		VOC Combustor*		Flare*		Pigging Station*	

## OTHER FACILITIES\*

Other Facility Type

Number

\*Those facilities indicated by an asterisk (\*) shall be used to determine the distance from the Production Facility to the nearest cultural feature on the Cultural Setbacks Tab.

Per Rule 303.b.(3)C, description of all oil, gas, and/or water pipelines:

Intra-facility flow lines generally 4" fusion bonded schedule 160 steel from WH to nearby Facility being permitted separately as it is 200' north of well pad to edge of Facility.

## CONSTRUCTION

Date planned to commence construction: 11/15/2014 Size of disturbed area during construction in acres: 3.70

Estimated date that interim reclamation will begin: 04/15/2015 Size of location after interim reclamation in acres: 0.45

Estimated post-construction ground elevation: 4937

## DRILLING PROGRAM

Will a closed loop system be used for drilling fluids: Yes

Is H<sub>2</sub>S anticipated? No

Will salt sections be encountered during drilling: No

Will salt based mud (>15,000 ppm Cl) be used? No

Will oil based drilling fluids be used? No

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Method: Commercial Disposal

Cutting Disposal: OFFSITE

Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: or Document Number:

Centralized E&P Waste Management Facility ID, if applicable:

## SURFACE & MINERALS & RIGHT TO CONSTRUCT

Name: NGL Water Solutions DJ

Phone: 303-815-1010

Address: 3773 Cherry Creek Dr. North, Suite  
1000

Fax: \_\_\_\_\_

Address: \_\_\_\_\_

Email: \_\_\_\_\_

City: Denver State: CO Zip: 80209

Surface Owner: ☒ Fee ☐ State ☐ Federal ☐ Indian

Check all that apply. The Surface Owner: ☐ is the mineral owner

☐ is committed to an oil and Gas Lease

☐ has signed the Oil and Gas Lease

☒ is the applicant

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed from or produced to this Oil and Gas Location: No

The right to construct this Oil and Gas Location is granted by: applicant is owner

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

Date of Rule 306 surface owner consultation \_\_\_\_\_

## CURRENT AND FUTURE LAND USE

### Current Land Use (Check all that apply):

Crop Land: ☒ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☐ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): \_\_\_\_\_

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

### Future Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☒ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☐ Rangeland ☐ Timber ☐ Recreational ☒ Other (describe): UIC Facility

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

## CULTURAL DISTANCE INFORMATION

Provide the distance to the nearest cultural feature as measured from Wells or Production Facilities onsite.

	From WELL	From PRODUCTION FACILITY
Building:	505 Feet	Feet
Building Unit:	505 Feet	Feet
High Occupancy Building Unit:	5280 Feet	Feet
Designated Outside Activity Area:	5280 Feet	Feet
Public Road:	220 Feet	Feet
Above Ground Utility:	205 Feet	Feet
Railroad:	1437 Feet	Feet
Property Line:	234 Feet	Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of nearest Well or edge of nearest Production Facility to nearest of each cultural feature as described in Rule 303.b.(3)A.
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.
- For measurement purposes only, Production Facilities should only include those items with an asterisk(\*) on the Facilities Tab.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit.
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 09/05/2014

## FOR MULTI-WELL PADS AND PRODUCTION FACILITIES WITHIN DESIGNATED SETBACK LOCATIONS ONLY:

- ☐ Check this box if this Oil and Gas Location has or will have Production Facilities that serve multiple wells (onl or offsite) and the Production Facilities are proposed to be located less than 1,000 feet from a Building Unit. *(Pursuant to Rule 604.c.(2)E.i., the operator must evaluate alternative locations for the Production Facilities that are farther from the Building Unit, and determine whether those alternative locations were technically feasible and economically practicable for the same proposed development.)*
- ☐ By checking this box, I certify that no alternative placements for the Production Facilities, farther from the nearest Building Unit, were available based on the analysis conducted pursuant to Rule 604.c.(2)E.i.

In the space below, explain rationale for siting the multi-well Production Facility(ies) that supports your Rule 604.c.(2)E.i determination. Attach documentation that supports your determination to this Form 2A.

## SOIL

List all soil map units that occur within the proposed location. attach the National Resource Conservation Service (NRCS) report showing the "Map Unit Description" report listing the soil typical vertical profile. This data is to be used when segregating topsoil.

The required information can be obtained from the NRCS web site at <http://soildatamart.nrcs.usda.org/> or from the COGCC web site GIS Online map page found at <http://colorado.gov/cogcc>. Instructions are provided within the COGCC web site help section.

NRCS Map Unit Name: Colby loam #15

NRCS Map Unit Name: \_\_\_\_\_

NRCS Map Unit Name: \_\_\_\_\_

## PLANT COMMUNITY:

Complete this section only if any portion of the disturbed area of the location's current land use is on non-crop land.

Are noxious weeds present: Yes ☐ No ☒

Plant species from: ☐ NRCS or, ☐ field observation Date of observation: \_\_\_\_\_

List individual species:

### Check all plant communities that exist in the disturbed area.

- ☐ Disturbed Grassland (Cactus, Yucca, Cheatgrass, Rye)
- ☐ Native Grassland (Bluestem, Grama, Wheatgrass, Buffalograss, Fescue, Oatgrass, Brome)
- ☐ Shrub Land (Mahogany, Oak, Sage, Serviceberry, Chokecherry)
- ☐ Plains Riparian (Cottonwood, Willow, Aspen, Maple, Poplar, Russian Olive, Tamarisk)
- ☐ Mountain Riparian (Cottonwood, Willow, Blue Spruce)
- ☐ Forest Land (Spruce, Fir, Ponderosa Pine, Lodgepole Pine, Juniper, Pinyon, Aspen)
- ☐ Wetlands Aquatic (Bullrush, Sedge, Cattail, Arrowhead)
- ☐ Alpine (above timberline)
- ☐ Other (describe): \_\_\_\_\_

## WATER RESOURCES

Is this a sensitive area: ☒ No ☐ Yes

Distance to nearest

downgradient surface water feature:  Feet

water well:  Feet

Estimated depth to ground water at Oil and Gas Location  Feet

Basis for depth to groundwater and sensitive area determination:

Distance to nearest: Downgradient surface water feature is Jim Creek which is across CR 16 to the southwest. Nearest Water Well is Permit #43538-MH (A Monitoring Well), which is approx 483' to the northeast, does not show a static well level. The next nearest Water Well is Permit #231051, to the Northwest, having a static water level of 389' and a depth of 900'.

Is the location in a riparian area: ☒ No ☐ Yes

Was an Army Corps of Engineers Section 404 permit filed ☒ No ☐ Yes If yes attach permit.

Is the location within a Rule 317B Surface Water Supply Area buffer  zone:

If the location is within a Rule 317B Surface Water Supply Area buffer have all public water supply systems within 15 miles been notified: \_\_\_\_\_

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐

Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

Please use the attached Location Drawing for the distances to the nearest Cultural Items.  
The location is currently covered with 8' to 10' high corn and is scheduled to be harvested in the next couple of weeks - and we request that the location pictures can be submitted after the harvesting is completed - prior to pad being built.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.

Signed: \_\_\_\_\_ Date: 10/10/2014 Email: paul.gottlob@iptenergyservices.com

Print Name: Paul Gottlob Title: Regulatory & Engin. Tech.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

## Conditions Of Approval

**All representations, stipulations and conditions of approval stated in this Form 2A for this location shall constitute representations, stipulations and conditions of approval for any and all subsequent operations on the location unless this Form 2A is modified by Sundry Notice, Form 4 or an Amended Form 2A.**

## **Best Management Practices**

<b>No</b>	<b>BMP/COA Type</b>	<b>Description</b>
1	Planning	This will be a single well pad adjacent to a facility for the separation of hydrocarbons and waste, the separated produced water shall be filtered prior to injection.
2	Traffic control	Access road: The access road will be constructed to accommodate local emergency vehicles. This road will be maintained for access at all times.
3	General Housekeeping	Fencing requirements. A permanent fencing plan will be reviewed by the surface owner, & the applicant.
4	General Housekeeping	Removal of surface trash. All trash, debris and material not intrinsic to the operation of the oil and gas facility shall be removed and legally disposed of as is applicable.
5	Material Handling and Spill Prevention	Leak Detection Plan. Pumper will visit the location daily and visually inspect all tanks and fittings for leaks. Additionally, monthly documented SPCCP inspections are conducted pursuant to 40 CFR §112.
6	Material Handling and Spill Prevention	Berm construction. Tank berms shall be constructed of steel rings with a synthetic or engineered liner and designed to contain 150% of the capacity of the largest tank. All berms will be visually checked periodically to ensure proper working condition.
7	Material Handling and Spill Prevention	Load-lines. All load-lines shall be bull-plugged or capped.
8	Material Handling and Spill Prevention	Tank specifications. Tanks will be designed, constructed and maintained in accordance with NFPA Code 30. The tanks are visually inspected once a day for issues, and recorded inspections are conducted once a month.
9	Noise mitigation	Lighting abatement measures shall be implemented, including the installation of lighting shield devices on all of the more conspicuous lights, low density sodium lighting where practicable; and rig shrouding will be used as well as sound walls on the west side during drilling and completion activities to provide noise relief, as the nearest building unit is just over 500' to the west. Permanent equipment on location shall be muffled to reduce noise, or shall be appropriately buffered.
10	Odor mitigation	Per Rule 805: Oil & gas facilities and equipment shall be operated in such a manner that odors and dust do not constitute a nuisance or hazard to public welfare.
11	Drilling/Completion Operations	Closed Loop Drilling Systems – Pit Restrictions. Not applicable; a closed-loop system will be used for drilling.
12	Drilling/Completion Operations	Green Completions – No hydrocarbons will be produced from this well – NA.
13	Drilling/Completion Operations	Blowout preventer equipment (“BOPE”). A double ram and annular preventer will be used during drilling. At least the drilling company shall have a valid well blowout prevention certifications. Stabbing valves shall be installed in the event of reverse circulation and shall be prior tested with low and high pressure fluid.
14	Drilling/Completion Operations	Drill stem tests. Not applicable; no Drill Stem tests are planned.
15	Drilling/Completion Operations	Control of fire hazards. All materials which are considered fire hazards shall be a minimum of 25' from the wellhead tanks or separators. Electrical equipment shall comply with API RP 500 and will comply with the current national electrical code. An emergency response plan has been generated for this site.
16	Drilling/Completion Operations	Guy line anchors. All guy line anchors shall be brightly marked pursuant to Rule 604.c (2)Q.
17	Final Reclamation	Well site cleared. Within 90-day subsequent to the time of plugging and abandonment of the entire site, superfluous debris and equipment shall be removed from the site.
18	Final Reclamation	P&A'd wells shall be identified pursuant to 319.a.(5).

Total: 18 comment(s)

### Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400702651	FORM 2A SUBMITTED
400702890	OTHER
400705863	ACCESS ROAD MAP
400705872	HYDROLOGY MAP
400705893	OTHER
400705894	OTHER
400705895	LOCATION DRAWING
400705904	OTHER
400706153	FACILITY LAYOUT DRAWING
400706158	WASTE MANAGEMENT PLAN
400706160	OTHER
400706199	NRCS MAP UNIT DESC

Total Attach: 12 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Return to draft as per operator's request.	10/10/2014 2:02:09 PM

Total: 1 comment(s)