

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400702491

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 8960
2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY
3. Address: 410 17TH STREET SUITE #1400
City: DENVER State: CO Zip: 80202
4. Contact Name: Olga Chikaloff
Phone: (720) 440-1600
Fax: (720) 279-2331
Email: ochikaloff@bonanzacrk.com

5. API Number 05-123-39462-00
6. County: WELD
7. Well Name: PRONGHORN
Well Number: K-O-12HNB
8. Location: QtrQtr: NWNE Section: 12 Township: 5N Range: 61W Meridian: 6
9. Field Name: NORTH RIVERSIDE Field Code: 60130

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 08/15/2014 End Date: 08/16/2014 Date of First Production this formation: 09/22/2014

Perforations Top: 6479 Bottom: 10713 No. Holes: Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☒

18 Stage Niobrara pumped a total of 54,488 bbls of fluid (Phaser) and 4,194,780 # of sand (40/70 Ottawa, 30/50 Ottawa, 20/40 InnoProp); ATP 4,497 psi, ATR 51.00 bpm, Final ISDP 2,769 psi; completed with sliding sleeves and casing packers.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 54488 Max pressure during treatment (psi): 5002

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.33

Type of gas used in treatment: Min frac gradient (psi/ft): 0.90

Total acid used in treatment (bbl): Number of staged intervals: 18

Recycled water used in treatment (bbl): 3426 Flowback volume recovered (bbl): 13901

Fresh water used in treatment (bbl): 51062 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 4194780 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 09/24/2014 Hours: 72 Bbl oil: 399 Mcf Gas: 687 Bbl H2O: 1836

Calculated 24 hour rate: Bbl oil: 133 Mcf Gas: 229 Bbl H2O: 612 GOR: 1722

Test Method: Flowing Casing PSI: 945 Tubing PSI: 189 Choke Size: 21/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1311 API Gravity Oil: 43

Tubing Size: 2 + 3/8 Tubing Setting Depth: 6222 Tbg setting date: 08/20/2014 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Olga Chikaloff

Title: Engineering Technician Date: _____ Email: ochikaloff@bonanzacrk.com
:

Attachment Check List

Att Doc Num **Name**

--	--

Total Attach: 0 Files

General Comments

User Group **Comment** **Comment Date**

--	--	--

Total: 0 comment(s)