



ESTIMATED EARTHWORK QUANTITIES (cy)				
ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	38310	17260	5990	15060
PIT	15730			15730
TOTALS	54040	17260	5990	30790

*NOTE:
1.) 10% Swell Factor Applied to Earthwork Cut Volume.
2.) Topsoil Volume Based on 12" Soil Depth.
3.) Total Disturbed Area = ±5.88 ac.

136 East Third Street
Rifle, Colorado 81650
Ph. (970) 625-2720
Fax (970) 625-2773



BOOKCLIFF
Survey Services, Inc.

SCALE: 1" = 80'
DATE: 9/24/14
PLAT: 2 of 7
PROJECT: Valley
DFT: cs

Construction Plan Prepared for:
WPXENERGY WPX Energy Rocky Mountain, LLC
MV 5-10 Drill Pad - Plat 2
Facility Layout Drawing