

FORM  
2

Rev  
08/13

## State of Colorado

### Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400703296

**(SUBMITTED)**

Date Received:

#### APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: HUNZIKER

Well Number: 1C-28HZ

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: Cheryl Light

Phone: (720)929-6461

Fax: (720)929-7461

Email: cheryl.light@anadarko.com

#### RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

#### WELL LOCATION INFORMATION

QtrQtr: SWSE Sec: 28 Twp: 2N Rng: 67W Meridian: 6

Latitude: 40.103228

Longitude: -104.891958

Footage at Surface: 433 feet FNL/FSL FSL 1593 feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 5049

County: WELD

GPS Data:

Date of Measurement: 08/04/2014 PDOP Reading: 1.6 Instrument Operator's Name: ROB WILSON

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FSL 497 FEL 460 FNL 510 FEL

Sec: 28 Twp: 2N Rng: 67W Sec: 28 Twp: 2N Rng: 67W

#### LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 2 North, Range 67 West, 6th P.M.  
Section 28: SE/4  
Containing 160 acres, more or less  
Weld County, Colorado

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 729 Feet  
Building Unit: 923 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 433 Feet  
Above Ground Utility: 410 Feet  
Railroad: 5280 Feet  
Property Line: 385 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 09/10/2014

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 343 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

UNIT CONFIGURATION:  
2N67W SEC 28: E/2E/2  
2N67W SEC 33: NE/4NE/4

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		200	GWA

## DRILLING PROGRAM

Proposed Total Measured Depth: 13063 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 343 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☐ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Please see Comments section. Disposal description will not fit in space provided.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	1257	520	1257	0
1ST	8+3/4	7	26	0	8354	830	8354	0
1ST LINER	6+1/8	4+1/2	11.6	6505	13063			

☒ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

### OTHER DISPOSAL DESCRIPTION:

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids.

Cuttings disposal: The surface owner has agreed to disposal of water-based cuttings onsite using bioremediation/solidification product.

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Ronett Powers

Title: Regulatory Analyst II Date: \_\_\_\_\_ Email: djregulatory@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_  
Expiration Date: \_\_\_\_\_

API NUMBER

05

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

## Best Management Practices

No	BMP/COA Type	Description
1	Planning	604c.(2).E. Multiwell Pads: In order to reduce surface impact, this application is for a twelve-well pad.
2	Planning	604c.(2).Q. Guy Line Anchors: Should guy line anchors be left buried for future use, they shall be identified by a bright marker greater than four (4) feet high and no more than one (1) foot east of the guy line anchor.
3	Planning	604c.(2).R. Tank Specifications: A geosynthetic liner will be laid under the tanks on this location and a metal containment will be constructed. Storage tanks will be designed, constructed and maintained in accordance with National Fire Protection Association (NFPA) Code 30 (2008 version). KMG will maintain written records to verify proper design, construction and maintenance. All records will be available for inspection by the Director.



4	Planning	604c.(2).S. Access Roads: KMG will utilize a lease access road from County Road 16 for drilling operations and maintenance equipment. The road will be properly constructed and maintained to accommodate for local emergency vehicle access. Water will be placed on dirt access roads to mitigate dust as needed. If feasible, magnesium chloride will also be used as needed on access roads to further abate dust.
5	Planning	604c.(2).V. Development From Existing Well Pads: Drilling from an existing well pad was not feasible for the development of the wells on this proposed oil and gas location; however, this well pad will be considered for future well locations.
6	Traffic control	604c.(2).D. Traffic Plan: If required by the local government, a traffic plan will be coordinated with the local jurisdiction prior to commencement of operations.
7	General Housekeeping	604c.(2).O. Loadlines: All loadlines shall be bullplugged or capped.
8	General Housekeeping	604c.(2).P. Removal of Surface Trash: A commercial size trash bin for removing debris will be located on site. This bin will be for use by all parties affiliated with the operation.
9	Storm Water/Erosion Control	604c.(2).W. Site-Specific Measures: KMG maintains a Storm Water Management Plan that assesses erosion control for every KMG operated location. This location will be added to this plan once construction begins. This site will be inspected every fourteen (14) days during construction activities, every thirty (30) days after construction is completed, and after any major weather event.
10	Material Handling and Spill Prevention	604c.(2).F. Leak Detection Plan: Automation technology will be utilized at this facility. This technology includes the use of fluid level monitoring for the tanks and produced water sumps, high-level shut offs, and electronic sensors to monitor the interstitial space of double-walled produced water sumps. All automation is monitored by Kerr-McGee's Integrated Operations Center (IOC), which is manned 24 hours per day, 7 days per week.
11	Material Handling and Spill Prevention	604c.(2).N. Control of Fire Hazards: KMG and its contractors will employ best management practices during the drilling and production of its wells and facilities and will comply with appropriate COGCC rules concerning safety and fire. KMG will ensure that any material that might be deemed a fire hazard will remain no less than twenty-five (25) feet from the wellhead(s), tanks and separator(s).
12	Construction	604c.(2).G. Berm Construction: A geosynthetic liner will be laid under the tanks on this location and a metal containment will be constructed. Berms or other secondary containment devices will be constructed around crude oil, condensate, and produced water storage tanks and shall enclose an area sufficient to contain and provide secondary containment for 150% of the largest single tank.
13	Construction	604c.(2).G. Berm Construction: Kerr-McGee will create tertiary containment by construction of a berm or diversion dike, site grading, or other comparable measures sufficient to further protect the ditch located 431' S of the proposed oil and gas location.
14	Construction	604c.(2).M. Fencing Requirements: The completed wellsites will be surrounded with a fence and gate with adequate lock to restrict access to authorized personnel only. KMG personnel will monitor the wellsites regularly upon completion of the wells. Authorized representatives and/or KMG personnel shall be on-site during drilling and completion operations.
15	Noise mitigation	604c.(2).A. Noise: Sound surveys that have been conducted on each rig type are utilized to anticipate any additional noise mitigation once a drilling rig is determined.
16	Drilling/Completion Operations	604c.(2).B. Closed Loop Drilling System: KMG will use a closed loop or "pitless" system for drilling and fluid management and will not construct a reserve pit.
17	Drilling/Completion Operations	604c.(2).C. Green Completions: KMG will install Vapor Recovery Unit(s) (VRU) to prevent uncontrolled venting of flash gas. Environmental Control Devices or Volatile Organic Compound Combustors (VOC) will be used to control working and breathing vapor losses for oil and water tanks. Temporary above ground polyethylene water pipelines will deliver water to location operations from larger trunk lines to reduce truck traffic and minimize air pollution.
18	Drilling/Completion Operations	604c.(2).H. BOPE: Our rigs at a minimum will have a double ram with blind and pipe ram; and annular preventer.

19	Drilling/Completion Operations	604c.(2).I. BOPE Testing for Drilling Operations: Upon initial rig-up, BOPEs will be tested at a minimum of every 30 days.
20	Drilling/Completion Operations	604c.(2).J. BOPE for Well Servicing Operations: Blowout prevention equipment will be used on any servicing operations associated with this well. Backup stabbing valves will be used during any future servicing operations during reverse circulation. Valves shall be pressure tested before each well servicing operation using low-pressure air and high-pressure fluid.
21	Drilling/Completion Operations	604c.(2).K. Pit Level Indicators: All tanks (used in lieu of pits) contain pit level monitors with Electronic Drilling Recorders (EDR). KMG uses EDRs with pit level monitor(s) and alarm(s) for production rigs. Basic level gauges are used on tanks utilized for the surface rig.
22	Drilling/Completion Operations	604c.(2).L. Drill Stem Tests: No drill stem tests are planned and none will be performed without prior approval from the Director.
23	Drilling/Completion Operations	Kerr McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
24	Drilling/Completion Operations	<p>Prior to drilling operations, Operator may perform an anti-collision review of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision review may include MWD or gyro surveys and surface locations of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well may only be drilled if the anti-collision review results indicate that the risk of collision is sufficiently low as defined by the anti-collision plan, with separation factors greater than 1.5, or if the risk of collision has been mitigated through other means including shutting in wells, plugging wells, increased drilling fluid in the event of lost returns or as is appropriate for the specific situation. In the event of an increased risk of collision, that risk will be mitigated to prevent harm to people, the environment or property. For the proposed well, upon conclusion of drilling operations, an as-constructed directional survey will be submitted to COGCC with the Form 5.</p> <p>Please see the attached 318A.n letter for a list of well(s) identified by the operator as being within 150 feet of the proposed well(s). If no letter is attached, the operator has not identified any wells as being within 150 feet of the proposed well(s) at the time of permitting.</p>
25	Final Reclamation	604c.(2).T. Well Site Cleared: The wellsite will be cleared of all non-essential equipment within ninety (90) days after all wells associated with the pad have been plugged and abandoned.
26	Final Reclamation	604c.(2).U. Identification of Plugged and Abandoned Wells: Pursuant to rule 319.a.(5)., once the well has been plugged and abandoned, KMG will identify the location of the wellbore with a permanent monument that will detail the well name and date of plugging.

Total: 26 comment(s)

### **Attachment Check List**

<u>Att Doc Num</u>	<u>Name</u>
400706604	OffsetWellEvaluations Data
400715436	DIRECTIONAL DATA
400715437	WELL LOCATION PLAT
400715438	PROPOSED SPACING UNIT
400715440	OPEN HOLE LOGGING EXCEPTION
400715441	EXCEPTION LOC REQUEST
400715444	DEVIATED DRILLING PLAN
400715462	SURFACE AGRMT/SURETY
400715464	EXCEPTION LOC WAIVERS
400717551	OTHER

Total Attach: 10 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)