

Noble Energy, INC
MERRIL # 1
05-123-05617

Proposed Wellbore Schematic

Re-enter and re-plug
KB elev - 4873'
GL elev - 4863'

Weld cap on 10 3/4" sur csg

10 3/4" sur csg set @ 297'
w/ 79 sks of cmt

Deepest Water well: 300'

Base Fox Hills 669'

385 sk cmt plug from 719' to surface

100 sk cmt plug set @ 3000'

NO PROD CSG
open hole to TD

75 sk cmt plug set @ 6792' (existing)

TD = 6792'