

FORM  
2

Rev  
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400696395

Date Received:

10/06/2014

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refiling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Puckett

Well Number: 13C-1

Name of Operator: CAERUS PICEANCE LLC

COGCC Operator Number: 10456

Address: 600 17TH STREET #1600N

City: DENVER State: CO Zip: 80202

Contact Name: Crissy Venturo

Phone: (720)352-7916

Fax: ( )

Email: cventuro@progressivepcs.net

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20130021

WELL LOCATION INFORMATION

QtrQtr: 66 Sec: 2 Twp: 7S Rng: 97W Meridian: 6

Latitude: 39.475658

Longitude: -108.180247

Footage at Surface: 2233 feet FNL/FSL FNL 634 feet FEL/FWL FEL

Field Name: WILDCAT

Field Number: 99999

Ground Elevation: 8478

County: GARFIELD

GPS Data:

Date of Measurement: 08/19/2014 PDOP Reading: 1.3 Instrument Operator's Name: Harold Marshall

If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL

1899 FSL 745 FWL 1899 FSL 745 FWL  
Sec: 1 Twp: 7S Rng: 97W Sec: 1 Twp: 7S Rng: 97W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

ALL of Section 1, T72, 97W, the E2/E2 of Section 2, 7S, 97W and additional portions of 6S, 97W and 6S, 96W and 7S, 96W. Please see attached mineral lease map.

Total Acres in Described Lease: 5141 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 2070 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 5280 Feet

Above Ground Utility: 5280 Feet

Railroad: 5280 Feet

Property Line: 4650 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 270 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 745 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

The WFCM is the target formation for this well.

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-21	640	All

## DRILLING PROGRAM

Proposed Total Measured Depth: 9103 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 270 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

If cuttings meet Table 910 they will be beneficially reused.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	52.8	0	75	108	75	0
SURF	14+3/4	9+5/8	36	0	2500	1172	2500	0
1ST	8+3/4	4+1/2	11.6	0	9103	741	9103	

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments First String / Production will be > 500 feet above TOG. Distance to nearest well completed in the same formation / permitted or existing well penetrating objective formation was measured to the proposed Puckett 13B-1. The distance to lease line was measured from the BHL to the west of the Puckett 5,141 acre lease. Please see the BMPs attached to the Form 2A Location Assessment for this well pad (Doc # 400697721).

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Crissy Ventura

Title: Permit Representative Date: 10/6/2014 Email: cventura@progressivepcs.net

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 11/14/2014

Expiration Date: 11/13/2016

### API NUMBER

05 045 22628 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

	Open hole resistivity and gamma logs shall be run to describe the stratigraphy of the entire well bore and to adequately verify the setting depth of surface casing and aquifer coverage. On a multi-well pad, these open hole logs are only required on one of the first wells drilled on the pad and the Drilling Completion Report - Form 5 for every well on the pad shall identify which well was logged.
	1)Operator shall comply with the most current revision of the Northwest Colorado Notification Policy. See attached notice.  2)Operator shall comply with the most current revision of the Garfield County Rulison Field Notice to Operators, with the following exception: all field notice requirements specified in this notice to operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see condition of approval #1). See attached notice.  3)Operator shall provide cement coverage from the production casing shoe (4+1/2" FIRST STRING) to a minimum of 200' above all Mesa Verde Group (and Ohio Creek Formation, if present) oil, gas, and water-bearing sandstone and coalbed formations. Verify production casing cement coverage with a cement bond log.  4)Comply with all provisions of the June 12, 2008 Notice to Operators drilling wells within ¾ mile of the rim of the Roan Plateau in Garfield County – Pit Design, Construction and Monitoring Requirements. See attached notice.

## Best Management Practices

### No BMP/COA Type

### Description

--	--	--

## Applicable Policies and Notices to Operators

Piceance Rulison Field - Notice to Operators.
NW Colorado Notification Policy.
Notice Concerning Operating Requirements for Wildlife Protection.
Pit Design, Construction and Monitoring Requirements Within 3/4 mile of the Rim of the Roan Plateau.

## Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400696395	FORM 2 SUBMITTED
400696399	DIRECTIONAL DATA
400696400	DEVIATED DRILLING PLAN
400696401	WELL LOCATION PLAT
400696713	MINERAL LEASE MAP

Total Attach: 5 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	Evaluated existing offset wells within 1,500 feet of this wellbore. Offset wells target the MVRD formation. No mitigation required. The proposed surface casing is more than 50' below the depth of the deepest water well within 1-mile of the surface location when corrected for elevation differences. There are no water wells used for non-industrial purposes within a 1-mile radius of the surface location.	10/10/2014 2:00:02 PM
Permit	Passed Completeness	10/8/2014 9:31:22 AM

Total: 2 comment(s)