

FORM  
2

Rev  
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400678816

Date Received:

10/01/2014

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Federal GM

Well Number: 14-11

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: 1001 17TH STREET - SUITE #1200

City: DENVER

State: CO

Zip: 80202

Contact Name: Reed Haddock

Phone: (303)606-4086

Fax: (303)629-8268

Email: reed.haddock@wpxenergy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: \_\_\_\_\_

WELL LOCATION INFORMATION

QtrQtr: NESW Sec: 11 Twp: 7S Rng: 96W Meridian: 6

Latitude: 39.450268

Longitude: -108.078696

Footage at Surface: 2019 feet FNL/FSL FSL 2249 feet FEL/FWL FWL

Field Name: GRAND VALLEY

Field Number: 31290

Ground Elevation: 5792

County: GARFIELD

GPS Data:

Date of Measurement: 07/24/2014 PDOP Reading: 1.8 Instrument Operator's Name: J. Kirkpatrick

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
1078 FSL 993 FWL 1078 FSL 993 FWL  
Sec: 11 Twp: 7S Rng: 96W Sec: 11 Twp: 7S Rng: 96W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: \_\_\_\_\_

Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Lease attached.

Total Acres in Described Lease: 2358 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC27874

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 993 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 2414 Feet  
Building Unit: 2414 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 4627 Feet  
Above Ground Utility: 2540 Feet  
Railroad: 5280 Feet  
Property Line: 1642 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 361 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 1559 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

CA COC45093, MVRD, N2, Sec. 11, 322 acres.

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-9	10	Sec 11 W2,W2E2,SENE

## DRILLING PROGRAM

Proposed Total Measured Depth: 6906 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 361 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Cuttings trench

Other Disposal Description:

Spent drilling fluids are treated with a de-watering unit. Separated mud solids are disposed with the drill cuttings in onsite cuttings trench. Separated water is re-used for drilling, or disposed at a permitted injection well.

Beneficial reuse or land application plan submitted?

Reuse Facility ID:  or Document Number:

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	18	48	0	60	25	60	0
SURF	13+1/2	9+5/8	32.3	0	1150	303	1150	0
1ST	8+3/4	4+1/2	11.6	0	6906	749	6906	3634

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 323872

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Reed Haddock

Title: Regulatory Specialist Sta Date: 10/1/2014 Email: reed.haddock@wpenergy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 11/15/2014

Expiration Date: 11/14/2016

### API NUMBER

05 045 22640 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

	1)Operator shall comply with the most current revision of the Northwest Colorado Notification Policy. See attached notice.  2)Operator shall comply with the most current revision of the Garfield County Rulison Field Notice to Operators, with the following exception: all field notice requirements specified in this notice to operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see condition of approval #1). See attached notice.  3)Operator shall provide cement coverage from the production casing shoe (4+1/2" FIRST STRING) to a minimum of 200' above all Mesa Verde Group (and Ohio Creek Formation, if present) oil, gas, and water-bearing sandstone and coalbed formations. Verify production casing cement coverage with a cement bond log.
--	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

## Best Management Practices

### No BMP/COA Type

### Description

1	Planning	WPX will run triple-combo open hole logs from well TD up to base of surface casing on one of the first wells drilled on a multi-well pad. Remaining wells on the pad will be logged with either cased hole pulsed neutron or triple-combo open hole. Every well will also have a CBL log from well TD up through well surface. Form 5 Completion Reports will identify wells on the pad with triple-combo open hole logs.
---	----------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Total: 1 comment(s)

### **Applicable Policies and Notices to Operators**

Piceance Rulison Field - Notice to Operators.

NW Colorado Notification Policy.

Notice Concerning Operating Requirements for Wildlife Protection.

### **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
400678816	FORM 2 SUBMITTED
400696685	WELL LOCATION PLAT
400696686	DEVIATED DRILLING PLAN
400696687	DIRECTIONAL DATA
400696693	OIL & GAS LEASE
400696729	TOPO MAP
400699572	FED. DRILLING PERMIT

Total Attach: 7 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Added verbiage to drilling & waste plans to match form 2A. Added Sec 11 to Unit configuration. Opr approved changes. Final review complete.	11/10/2014 8:40:49 AM
Engineer	Evaluated existing offset wells within 1,500 feet of this wellbore. Offset wells target the MVRD formation. No mitigation required. The proposed surface casing is more than 50' below the depth of the deepest water well within 1-mile of the surface location when corrected for elevation differences. The deepest water well within 1-mile is 60' deep and the surface elevation is about 5160' above sea level.	10/8/2014 9:09:03 AM
LGD	Pass: GDB	10/6/2014 3:26:34 PM
Permit	Passed Completeness	10/3/2014 1:06:14 PM

Total: 4 comment(s)