

Noble Energy, INC  
Best # 1  
05-123-05735

**Proposed Wellbore Schematic**

Re-enter and re-plug

KB elev - 4673'

GL elev - 4663'

Weld cap on 10 3/4" sur csg

10 3/4" sur csg set @ 164'  
w/ 177 sks of cmt

Base Fox Hills 483'

Deepest Water well: 1000'

NO PROD CSG  
open hole to TD

TD = 6312'

330 sk cmt plug from 633' to surface

50 sk cmt plug set @ 1150'

100 sk cmt plug set @ 3000'