

Well Name: WPX ENERGY RMT.
Well Name: FED BCU-542-30-198
Pad Name: FED BCU-33-30-198
Legal Description: Sec30T1NR98W
Unit: Barcus Creek Federal Unit
Unit # COC060831
COGCC # 96850
API # 05-103-11996-00
County: Rio Blanco
Field: Sulphur Creek
Field # 80090
Rig Name and Number: CYCLONE 29
WPX Supervisor: TOM BOWEN
Phone number at rig: 970-778-2201

RECEIVED
 SEP 03 2014
COGCC



This notice, sent on	09/03/2014	is to inform you that WPX E
ran and cemented	9.625 SURFACE	casing.
Depth casing landed	3,334'	
Volume pumped	lead 146.6/ tail 73.3/ tail 270.5	
Sack of cement used	465/210/775	
Cement density	12.8/12.8/12.8	
Yield cubic ft/sack	1.77/1.96/1.96	
Stages	2	
Lift Pressure	645 2 bbl/min/ 390 2bbl/min	psi
Bumped plug	YES/YES	
Bump pressure	1125 1st/ 1807 2nd	psi
Floats held	YES/YES	
Returns	FULL/FULL	
Losses	0	

Additionally:

Excess cement 30/60%. 51 bbls cement back 1st / 100 bbls cement back 2nd. Fell 28'. Topped out with 3.4 bbls 15.6# cement. Also topped out 40' BCU 23-30-198 with excess cement from 2nd stage.
 103-11995