

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400697941

(SUBMITTED)

Date Received:

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Colt

Well Number: A13-628

Name of Operator: NOBLE ENERGY INC

COGCC Operator Number: 100322

Address: 1625 BROADWAY STE 2200

City: DENVER

State: CO

Zip: 80202

Contact Name: Justin Garrett

Phone: (303)228 4449

Fax: (303)228 4286

Email: JDGarrett@nobleenergyinc.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030009

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 17 Twp: 6N Rng: 63W Meridian: 6

Latitude: 40.482150

Longitude: -104.468800

Footage at Surface: 1052 feet FNL/FSL FSL 424 feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4665

County: WELD

GPS Data:

Date of Measurement: 07/24/2014 PDOP Reading: 1.6 Instrument Operator's Name: Wyatt Hall

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FSL 624 FEL 1155 FSL 1240 FEL
Sec: 18 Twp: 6N Rng: 63W Sec: 13 Twp: 6N Rng: 64W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T6N-R63W Sec 17: SW/4, Sec 18: All that part of the E/2E/2 lying South of the UPRC ROW. Please see attached map.

Total Acres in Described Lease: 246 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1331 Feet
Building Unit: 1344 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5228 Feet
Public Road: 1039 Feet
Above Ground Utility: 1027 Feet
Railroad: 5280 Feet
Property Line: 424 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 08/11/2014

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 165 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 624 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Unit configuration = T6N-R63W Sec 18: S/2, T6N-R64W Sec 13: SE/4.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		480	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 12805 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 165 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Beneficial reuse

Other Disposal Description:

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: 2614238

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	0	0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	850	400	850	0
1ST	8+3/4	7	26	0	7057	480	7057	
1ST LINER	6+1/8	4+1/2	11.6	6907	12805			

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments 1st string top of cement is 200' above Niobrara. The production liner will be hung off inside 7" casing. The production facility will be permitted into this location: Colt A 13-611 Multi 2A (Doc 400697933). Noble Energy Inc. requests approval of Rule 318A.a Surface location outside window; 318A.c Twinning location exception, request letter attached. Waiver language is in attached SUA (Page 4, Section 5, Paragraph A).
Nearest producing well is the proposed Colt A13-625.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Justin Garrett

Title: Regulatory Analyst Date: _____ Email: RegulatoryNotification@noble

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Best Management Practices

No	BMP/COA Type	Description
1	General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
2	Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR- 038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place and maintained until the pad reaches final reclamation.
3	Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
4	Drilling/Completion Operations	<p>Anti-collision: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.</p> <p>During and Post stimulation: Noble Energy will comply with the COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated 5/29/12</p>

Total: 4 comment(s)

Attachment Check List

Att Doc Num	Name
400734042	OffsetWellEvaluations Data
400734045	DIRECTIONAL DATA
400734047	WELL LOCATION PLAT
400734048	DEVIATED DRILLING PLAN
400734049	SURFACE AGRMT/SURETY
400734057	EXCEPTION LOC REQUEST
400734058	PROPOSED SPACING UNIT
400737729	LEASE MAP

Total Attach: 8 Files

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)

