

US ROCKIES REGION

Anadarko Daily Summary Report

Well: HSR-TANDOWSKY 8-21

Project: COLORADO-WELD-NAD83-UTM13

Site: HSR-TANDOWSKY 8-21

Rig name no.: BASIC 1549/1549

Event: ABANDONMENT

Start date: 10/29/2014

End date: 11/25/2014

Spud date: 8/10/1989

Active datum: RKB @4,924.99usft (above Mean Sea Level)

UWI: 0/3/N/66/W/21/0/NESE/6/0/0/0/0/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	10/29/2014		MIRU Basic 1549. Kill well. ND well head. NU BOP. TOOH & tally tbg. SI. SDFN.
2	10/30/2014		RU Warrior. Run gauge ring. Set CIBP @ 7000'. TIH w/tbg to 7000'. RU Sanjel. Spot 30 sks G cmt from 7000' to 6484'. TOOH. RU Warrior. Shoot squeeze holes @ 4540' & 4100'. Set retainer @ 4110'. PU stinger & hydrotest tbg in hole. SI. SDFN.
3	10/31/2014		RU Sanjel. Squeeze Sussex from 4540' to 4100' w/200 sks G cmt. TOOH. RU Warrior. Cut csg @ 1200'. ND BOP. Unland csg. NU BOP. LD csg. TIH w/tbg to 1300'. RU Sanjel. Spot 250 sks Type III cmt from 1300' to 350'. LD tbq. SI. SDFN.
4	11/03/2014		ND BOP. RU Warrior. Tag cmt top @ 464'. Set 8 5/8" CIBP @ 80'. NU BOP. Test csg to 1000 psi. OK. ND BOP. RDMO.
5	11/25/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 78'. Filled casing stub with 25 bags 5000# cement. Capped casing with a metal plate containing well info. Backfilled.
6	11/25/2014		TIME : 14:30, ROUTE : N15, WINS: 74880, PROJECT TYPE: P&A, PROD: NB/CD, BATT#: 34002048, GATHERER: KMG, STATION: 45107, LINE : N/A, COMMENTS: P&A'd OFFLINE.