

Reagan LD06-685 Pad

T9N-R58W

Section 05: NENE

Weld County, Colorado, Northern Part

60—Shingle clay loam, 0 to 9 percent slopes

Map Unit Setting

Elevation: 3,600 to 5,500 feet
Mean annual precipitation: 10 to 13 inches
Mean annual air temperature: 46 to 48 degrees F
Frost-free period: 110 to 140 days

Reagan LD06-685, 680, 675, 670

Map Unit Composition

Shingle and similar soils: 80 percent
Minor components: 20 percent

Description of Shingle

Setting

Landform: Ridges, breaks, plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Calcareous, clayey loamy residuum weathered from shale

Typical profile

H1 - 0 to 4 inches: moderately alkaline, clay loam
H2 - 4 to 11 inches: moderately alkaline, clay loam
H3 - 11 to 15 inches: , unweathered bedrock

Properties and qualities

Slope: 0 to 9 percent
Depth to restrictive feature: 10 to 20 inches to paralithic bedrock
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat):
Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 15 percent
Salinity, maximum in profile: Nonsaline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Very low (about 2.1 inches)

Interpretive groups

Farmland classification: Not prime farmland
Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: D
Ecological site: Shaly Plains (R067BY045CO)

Minor Components

Renohill

Percent of map unit: 10 percent

Map Unit Description: Shingle clay loam, 0 to 9 percent slopes---Weld County, Colorado, Northern Part

Keota

Percent of map unit: 5 percent

Thedalund

Percent of map unit: 5 percent

Data Source Information

Soil Survey Area: Weld County, Colorado, Northern Part

Survey Area Data: Version 9, Dec 23, 2013