

FORM  
2  
Rev  
08/13

State of Colorado  
Oil and Gas Conservation Commission  
1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:  
400528334

APPLICATION FOR PERMIT TO:

Drill       Deepen       Re-enter       Recomplete and Operate

Date Received:  
10/10/2014

TYPE OF WELL    OIL     GAS     COALBED     OTHER \_\_\_\_\_  
ZONE TYPE      SINGLE ZONE     MULTIPLE ZONES     COMMINGLE ZONES

Refiling   
Sidetrack

Well Name: Tigertail Federal      Well Number: 2-3  
Name of Operator: GRYNBERG\* JACK DBA GRYNBERG PETROLEUM CO      COGCC Operator Number: 36200  
Address: 3600 S. YOSEMITE ST - STE 900  
City: DENVER      State: CO      Zip: 80237-1830  
Contact Name: Terry Hoffman      Phone: (720)542-8287      Fax: ( )  
Email: terry@rockymountainpermitting.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20100037

WELL LOCATION INFORMATION

QtrQtr: NWSE      Sec: 2      Twp: 7N      Rng: 64W      Meridian: 6  
Latitude: 40.600400      Longitude: -104.513760

Footage at Surface: 1982 feet      FNL/FSL      FSL      1985 feet      FEL/FWL      FEL

Field Name: WILDCAT      Field Number: 99999

Ground Elevation: 4887      County: WELD

GPS Data:  
Date of Measurement: 05/27/2014    PDOP Reading: 1.3    Instrument Operator's Name: Wyatt Hall

If well is  Directional       Horizontal (highly deviated)      **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL      FEL/FWL      Bottom Hole: FNL/FSL      FEL/FWL

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_      Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership:  Fee       State       Federal       Indian

The Surface Owner is:  is the mineral owner beneath the location.  
(check all that apply)  is committed to an Oil and Gas Lease.  
 has signed the Oil and Gas Lease.  
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is:  Fee       State       Federal       Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_      Surface Surety ID: \_\_\_\_\_

**LEASE INFORMATION**

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Lots 1 & 2 of Section 2-T7N-R64W  
S2/NE of Section 2-T7N-R64W  
SE/4 of Section 2-T7N-R64W

Total Acres in Described Lease: 320 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # COC67169

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 660 Feet

**CULTURAL DISTANCE INFORMATION**

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 5280 Feet

Above Ground Utility: 1945 Feet

Railroad: 5280 Feet

Property Line: 660 Feet

**INSTRUCTIONS:**

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

**DESIGNATED SETBACK LOCATION INFORMATION**

Check all that apply. This location is within a:  Buffer Zone  
 Exception Zone  
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

**SPACING and UNIT INFORMATION**

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 1367 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary \_\_\_\_\_ Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

**SPACING & FORMATIONS COMMENTS**

\_\_\_\_\_

**OBJECTIVE FORMATIONS**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL			
D SAND	DSND			
J SAND	JSND			
LYONS	LYNS			
NIOBRARA	NBRR			

**DRILLING PROGRAM**

Proposed Total Measured Depth: 9101 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 1367 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type:  Annular Preventor  Double Ram  Rotating Head  None

### GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

### DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

### CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	40	0	40	50	40	0
SURF	12+1/4	8+5/8	36	0	750	342	750	0
1ST	7+7/8	4+1/2	11.6	0	9101	1201	9101	1201

Conductor Casing is NOT planned

### DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

### GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

### RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments \_\_\_\_\_

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Terry L. Hoffman \_\_\_\_\_

Title: Permit Agent Date: 10/10/2014 Email: terry@rockymountainpermitting \_\_\_\_\_

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 12/6/2014

Expiration Date: 12/05/2016

### API NUMBER

05 123 40775 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

- 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU.
- 2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

## Best Management Practices

No	BMP/COA Type	Description
1	Storm Water/Erosion Control	<p>Grynberg Petroleum Company Tigertail Federal #2-3 NWSE Section 2-T7N-R64W Weld Co., Colorado</p> <p>Best Management Practices Summary</p> <p>Stormwater Management Plans (SWMP) will be in place to address construction, drilling and operations associated with Oil &amp; Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE). BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. The BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.</p> <p>Spill Prevention Control and Counter measures (SPCC) plans will be in place to address any possible spills associated with Oil &amp; Gas operations throughout the state of Colorado in accordance with CFR12.</p> <p>Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup will be required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup will consist of patrolling the roadways, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.</p> <p>The above BMP's will be provided to all Grynberg Petroleum Company, contractors and will be posted in the company trailer located on location during drilling, completion and production operations.</p>

Total: 1 comment(s)

### Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

### Attachment Check List

Att Doc Num	Name
400528334	FORM 2 SUBMITTED
400705412	WELL LOCATION PLAT
400705429	SURFACE AGRMT/SURETY
400705435	OIL & GAS LEASE

Total Attach: 4 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	12/2/2014 10:19:34 AM
Permit	Changed distance to nearest road per Location Drawing. ok to pass.	10/27/2014 11:08:51 AM
Permit	Passed Completeness	10/14/2014 11:51:11 AM

Total: 3 comment(s)