

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400727716

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100185

Contact Name: Bonnie Lamond

Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-5156

Address: 370 17TH ST STE 1700

Fax:

City: DENVER

State: CO

Zip: 80202-

API Number 05-123-37586-00

County: WELD

Well Name: Drieth

Well Number: 1A-6H-A368

Location: QtrQtr: NENE Section: 6 Township: 3N Range: 68W Meridian: 6

Footage at surface: Distance: 676 feet Direction: FNL Distance: 434 feet Direction: FEL

As Drilled Latitude: 40.260183 As Drilled Longitude: -105.038148

GPS Data:

Date of Measurement: 12/10/2014 PDOP Reading: 1.5 GPS Instrument Operator's Name: J.R. McGehee

** If directional footage at Top of Prod. Zone Dist.: 139 feet. Direction: FNL Dist.: 480 feet. Direction: FEL

Sec: 6 Twp: 3N Rng: 68W

** If directional footage at Bottom Hole Dist.: 72 feet. Direction: FNL Dist.: 482 feet. Direction: FWL

Sec: 6 Twp: 3N Rng: 68W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 08/16/2014 Date TD: 10/13/2014 Date Casing Set or D&A: 10/15/2014

Rig Release Date: 10/15/2014 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 11498 TVD** 6996 Plug Back Total Depth MD 11476 TVD** 6997

Elevations GR 5087 KB 5100 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

Encana Oil and Gas was granted permission for the omission of open-hole logs for the subject well—sufficient data from a nearby well meet state requirements.

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	16	65	0	93	128	0	93	
SURF	12+1/4	9+5/8	40	0	845	290	0	845	
1ST	8+3/4	7	26	0	7,292	713	0	7,292	
2ND	6+1/8	4+1/2	13.5	0	11,498	408	6,292	11,498	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
FOX HILLS BASE	300				
SUSSEX	3,524				
SHANNON	4,093				
TEEPEE BUTTES	6,000				
SHARON SPRINGS	7,044				
NIOBRARA	7,130				

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Bonnie Lamond

Title: Regulatory Analyst

Date: _____

Email: bonnie.lamond@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400749766	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400749769	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400749745	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400749750	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400749754	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400749771	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)