

**FORM
5**Rev
09/14**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400727719

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100185

Contact Name: Bonnie Lamond

Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-5156

Address: 370 17TH ST STE 1700

Fax:

City: DENVER

State: CO

Zip: 80202-

API Number 05-123-37585-00

County: WELD

Well Name: Drieth

Well Number: 1B-6H-A368

Location: QtrQtr: NENE Section: 6 Township: 3N Range: 68W Meridian: 6

Footage at surface: Distance: 686 feet Direction: FNL Distance: 434 feet Direction: FEL

As Drilled Latitude: 40.260155 As Drilled Longitude: -105.038149

GPS Data:

Date of Measurement: 10/10/2014 PDOP Reading: 2.2 GPS Instrument Operator's Name: JR McGehee

** If directional footage at Top of Prod. Zone Dist.: 475 feet. Direction: FNL Dist.: 773 feet. Direction: FEL

Sec: 6 Twp: 3N Rng: 68W

** If directional footage at Bottom Hole Dist.: 420 feet. Direction: FNL Dist.: 493 feet. Direction: FWL

Sec: 6 Twp: 3N Rng: 68W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 08/17/2014 Date TD: 10/02/2014 Date Casing Set or D&A: 10/03/2014

Rig Release Date: 10/15/2014 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 11617 TVD** 7202 Plug Back Total Depth MD 11599 TVD** 7203

Elevations GR 5087 KB 5100 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

Encana Oil and Gas was granted permission for the omission of open-hole logs for the subject well—sufficient data from a nearby well met state requirements.

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	16	65	0	93	128	0	93	
SURF	12+1/4	9+5/8	40	0	838	290	0	838	
1ST	8+3/4	7	26	0	7,717	635	0	7,717	
2ND	6+1/8	4+1/2	13.5	0	11,601	325	6,717	11,601	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
FOX HILLS BASE	370				
SUSSEX	3,910				
TEEPEE BUTTES	4,387				
SHARON SPRINGS	7,003				
NIOBRARA	7,066				
FORT HAYS	7,570				
CODELL	7,664				

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Bonnie Lamond

Title: Regulatory Analyst

Date: _____

Email: bonnie.lamond@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400749842	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400749844	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400749803	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400749840	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400749847	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400751008	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)