

Anadarko Daily Summary Report

Well: WILLIAMS 11-20

Project: COLORADO-WELD-NAD83-UTM13

Site: WILLIAMS 20-20 PAD

Rig Name No: BAYOU 12/12

Event: WELL WORK EXPENSE

Start Date: 10/24/2014

End Date:

Spud Date: 5/31/2009

Active Datum: KB @4,916.00usft (above Mean Sea Level)

UWI: 0/2/N/68/W/20/0/NWSE/6/PM/S/1,548.00/E/0/1,497.00/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	10/24/2014		CREW TRAVEL TO LOC, SPOT IN EQUIPMET, RU WO RIG, LEY DOWN PUMP AND TANK LINES, BLOW DOWN WELL, KILL WELL W/30/20 BBLS RD WH NU BOPS/ WORK FLOOR. MIRU EMI SERVICES, TOO H TESTING TBG, NO BAD, RDMO EMI SERVICES, PU RBP AND TIH SET RBP @7405' w/ 235JNTS,
2	10/27/2014		CREW TRAVEL TO LOC, OPEN WELL, ND WORK FLOOR/BOPS. RD WH, UNLAND 4.5 CASING, RU ANNULAR FLANGES, NU BOPS/ WORK FLOOR. WAITH FOR 1 1/4 TBG FROM A&W, PU MULE SHOE, TIH AND TAG @1205'. w/37JNTS, CIRCULATE 110 BBLS, CLOSE WELL CREW, TRAVEL TO YARD
3	10/28/2014		CREW TRAVEL TO LOC, OPEN WELL BRAKE CIRCULATION, CIRCULATE TOTAL OF 150BBLS, MIRU CEMENTERS, PUMP TOTAL OF 43.4BBLS OF TYPE III, 14.8 ppg, 1.33cuff/sx, RDMO CEMENTERS, LD 1 1/4 TBG, RD WORK FLOOR, ND BOPS, RELAND 4.5, RD ANNULAR FALNGES, RU WH, NU BOPS CLOSE WELL CREW TRAVEL TO YARD.
4	10/29/2014		CREW TRAVEL TO LOC, OPEN WELL, MIRU WIRELINE, LOG FROM 1500' TO 0' SEDN LOG TO EVANS OFFICE, PU RBP-HEAD TIH TAG SAND, BRAKE CIRCULATION WASH SAND OFF CIRCUALTER CLEAN, RELEASE RBP TOO H, LD RBP, PU XN, TIH AND TAG FILL @ 7919'. BRAKE CIRCULATION AND CLEAN
5	10/30/2014		CREW TRAVEL TO LOC, OPEN WELL, RD WORK FLOOR, ND BOPS, RU WH. MIRU HYDROTESTER, PRESSURE TEST TO 5000psi FOR 15 MIN, TEST GOOD, RDMO HYDROTESTER, PU LUBRICATOR, MAKE BROACH RUN TO XN, RU LUBRICATOR, CLOSE WELL, RD WO RIG, MOVE TO THE WILLIAMS 23-20.

COMMENTS:

10/24/14 - CIRCULATE GAS OUT AND PRESSURE TEST TO 1000psi FOR 15 MIN, TOO H, SPOT 2sx OF SAND ON TOP OF RBP, CLOSE WELL CREW TRAVEL TO YARD

10/29/14 - OUT TO PBRD 8042'. CIRCULATE CLEAN, LD EXTRA JNTS, LAND TBG @ 7824'. w/248 JOINTS. CLOSE WELL, SDFN, CREW TRAVEL TO YARD