

US ROCKIES REGION			
Anadarko Daily Summary Report			
Well: PSC 32-9			
Project:COLORADO-WELD-NAD83-UTM13		Site:PSC 32-9	Rig name no.:BASIC 1549/1549
Event: ABANDONMENT		Start date: 11/3/2014	End date: 11/25/2014
Active datum: KB @4,771.00usft (above Mean Sea Level)		Spud date: 1/12/1994	
UWI: 0/3/N/67/W/9/0/NESW/6/0/0/0/0/0/0/0			
Report no.	Report date	MD (usft)	24 hr summary
1	11/03/2014		MIRU Basic 1549. Kill well. ND well head. NU BOP. TOO. RU Warrior. Run gauge ring to 7130'. Set 3.5" CIBP @ 7120'. Dump bail 1 sks cmt on CIBP. Set CIBP @ 6820'. SI. SDFN.
2	11/04/2014		TIH w/tbg to 6820'. Circ well. Test csg to 1000 psi. OK. Wait on cmt. RU Sanjel. Set cmt plug from 6820' to 6150' w/25 sks Thermal 35 cmt. LD csg. RU Warrior. Shoot squeeze holes @ 4200'. ND BOP. RU Sanjel w/cmt head. (See Remarks)
3	11/05/2014		RU Warrior. Tag cmt top @ 3612'. Cut off csg @ 750'. Circ well. LD csg. TIH w/tbg to 850'. RU Sanjel. Spot plug from 850' to 155' e/280 sks Type III cmt. ND BOP. LD tbg. Wait on cmt. RU Warrior. Tag cmt @ 155. Set * 5/8" CIBP @ 80'. Test OK. RDMO.
4	11/24/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 84'. Filled casing stub with 38 bags 5000# cement. Capped casing with a metal plate containing well info. Backfilled.
5	11/25/2014		TIME : 15:00, ROUTE : N23, WINS: 75671, PROJECT TYPE: P&A, PROD: NB/CD/J, BATT#: 34003335, GATHERER: DCP, STATION: 232765, LINE : N/A, COMMENTS: P&A'd OFFLINE.

REMARKS:

11/04/14 - Squeeze Sussex from 4200' to 3600' w/280 sks G cmt. Displace to 3600'. SI. SDFN.