

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400745258

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100185

Contact Name: Toby Sachen

Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-5845

Address: 370 17TH ST STE 1700

Fax:

City: DENVER

State: CO

Zip: 80202-

API Number 05-123-38444-00

County: WELD

Well Name: Bohrer

Well Number: 2B-19H-E368

Location: QtrQtr: SWNW Section: 19 Township: 3n Range: 68w Meridian: 6

Footage at surface: Distance: 1372 feet Direction: FNL Distance: 762 feet Direction: FWL

As Drilled Latitude: 40.214451 As Drilled Longitude: -105.052447

GPS Data:

Date of Measurement: 11/25/2014 PDOP Reading: 2.1 GPS Instrument Operator's Name: Chris Bettencourt

** If directional footage at Top of Prod. Zone Dist.: 490 feet. Direction: FNL Dist.: 777 feet. Direction: FWL

Sec: 19 Twp: 2n Rng: 68w

** If directional footage at Bottom Hole Dist.: 529 feet. Direction: FNL Dist.: 488 feet. Direction: FEL

Sec: 19 Twp: 3n Rng: 68w

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 05/05/2014 Date TD: 05/21/2014 Date Casing Set or D&A: 05/22/2014

Rig Release Date: 07/14/2014 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 11588 TVD** 7128 Plug Back Total Depth MD 11569 TVD** 7127

Elevations GR 5060 KB 5092

Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, MWD, Open Hole Logs run on the Bohrer 2F-19H-E368.

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	16	30	0	112	114	0	112	
SURF	12+1/4	9+5/8	40	0	867	360	0	880	
1ST	8+3/4	7	26	0	7,593	652	0	7,593	
2ND	6+1/8	4+1/2	13.5	0	11,570	500	5,100	11,570	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,786				
NIOBRARA	6,876				
FORT HAYS	7,409				
CODELL	7,497				

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Toby SachenTitle: Regulatory Analyst Date: _____ Email: toby.sachen@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400753981	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400753994	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400754086	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400754087	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400754102	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400754116	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400754241	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)