

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: HSR-RADEMACHER 12-30

Project: COLORADO-WELD-NAD83-UTM13

Site: RADEMACHER 12-30 PAD

Rig name no.: LEED 724/724

Event: ABANDONMENT

Start date: 11/10/2014

End date: 12/4/2014

Spud date: 1/14/1995

Active datum: RKB @4,866.00usft (above Mean Sea Level)

UWI: 0/3/N/67/W/30/0/SWNNW/6/0/0/0/0/0/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	11/06/2014		MIRU SUMMIT SL RIH TAG @ 7162' COULD NOT FISH TOOLS. RDMO
2	11/10/2014		MIRU Leed 724 500/500/ 0 Blew down well & controlled it. NDWH-NUBOP Ru work floor TOO H & tally out 219 jts SWI drained pump & lines SDFN
3	11/11/2014		RU Warrior WL RIH G-ring to 6950' set CIBP @ 6920' RDWL RU Hole Seeker tester TIH tested tbg in to 6920' RD tester circulated well PT CIBP to 1000/15 mins held good PUH 8 jts SWI drained pump & lines SDFN
4	11/12/2014		TIH 8 jts to 6910' circulated well, RU Baker pumped 40 sks class G cmt 15.8 ppg, 1.36 cf/sk PUH to 4950' pumped 50 sks class G cmt 15.8 ppg, 1.15 cf/sk RD Baker TOO H SWI drained pump & lines SDFN
5	11/13/2014		Started engines thawed out WH valves & BOP, airlines problems on rig SDFN
6	11/14/2014		Started engines, TIH tag TOC @ 4150' called for more cmt per Ed Griebel. Circulated well & waited for Sanjel due to short notice. RU Sanjel pumped 25 sks class G cmt 15.8 ppg, 1.15 cf/sk RD Sanjel TOO H SWI SDFN
7	11/17/2014		RU Warrior WL RIH tag TOC @ 3136' jet cut csg @ 950' RDWL NDBOP & WH unlanded csg NUspool & BOP RU 3 1/2 tools circulated well TOO H LD 950' of csg TIH 2 1/16 tbg to 950' circulated RU Baker pumped 10 bbls SAPP & 180 sks type 3 cmt 14.8...1.33 TOO H SDFN.
8	11/18/2014		TIH tag TOC @ 543' TOO H tbg NDBOP & spool, RU Warrior WL set 8 5/8 CIBP @ 90' RDWL NU Spool PT CIBP, plug did not hold pressure, call for Pkr & 2 7/8 tbg (per David Dalton) TIH pkr set @ 85' PT plug held 1000 psi/15mins. TOO H TIH tbg SEE REMARKS
9	11/19/2014		Tag TOC @ 12' in ND BOP & spool RDMO Leed 724
10	12/04/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ surface, no additional cement needed. Capped casing with a metal plate containing well info. Backfilled.
11	12/04/2014		TIME : 10:30, ROUTE : W24, WINS: 74634, PROJECT TYPE: P&A, PROD: NB/CD, BATT#: 34003711, GATHERER: KMG, STATION: 8101, LINE : N/A, COMMENTS: P&A'd OFFLINE. NB/CD

## REMARKS:

11/18/14 - to 85' Waited for Sanjel, RU Sanjel pumped 45 sks type 3 CMT 14.8 ppg, 1.33 cf/sk. pumped 7 bbls of cmt got cmt up to surface LD tbg squeeze into hole 2 bbls of cmt SWI with 52 psi. RD Sanjel SDFN